

## Construction Method Statement

1. Working hours will be 8:00 to 18:00 Monday to Friday and 8am to 1pm Saturdays if required. Deliveries will be accepted within these working hour periods except Bank Holidays. No working of any kind permitted on Sundays or any Public/Bank Holidays. No vehicle connected with the works to arrive on site before 07:30 or leave after 19:00 (except in the case of emergency).
2. All loading and unloading of material will take place on the site whenever possible so as not to obstruct traffic.
3. On-site parking will be available for contractors at all times.
4. The perimeters of the site will be fenced off with Heras fencing. The fence to the front boundary will be fitted with gates which will be secured when the site is vacated. Appropriate safety notices will be displayed. A secure compound for the storage of materials will be formed on the site.
5. Wheel washing facilities will be made available on site and all vehicles will be checked and washed down as necessary before leaving the site to minimise any site debris being transferred onto the highway. Regular inspection of the adjacent road will be carried out to ensure that no debris is inadvertently spread on to the highway. Clean edges of roads and footpaths using hand broom with controlled damping.
6. The Contractors will seek to monitor and control the effects of dust on site during the construction process and to consider the proximity of dust sensitive properties in the vicinity of the works. Ensure that a water supply is available for damping down. Store fine materials such as sand and cementitious products under cover or in sealed containers. Covers will be put on to skips before leaving site that contain dusty material. No materials produced as a result of the site development or clearance shall be burned on site.
7. Noise Control - The selection and use of machinery to operate on site, and working practices to be adopted will, as a minimum requirement, be compliant with the standards laid out in British Standard 5228:2014. 3. Mobile plant to be resident on site during extended works shall be fitted with non-audible reversing alarms (subject to HSE agreement). Prior to the commencement of any piling works a rationale for the piling method shall be chosen and details of the techniques to be employed which aim to minimise noise and vibration to nearby residents.
8. All site operatives and sub-contractors are to be made aware of their requirement to assist in the implementation of these requirements and to work to the following best practice measures:

Environmental Agency - General guide to the prevention of pollution

Environmental Agency - Works in, near or liable to affect watercourses

Environmental Agency - Working at demolition and construction sites