

#### **Masonry Schedule**



Below ground to be 100mm Min 7.3 N/mm2 Above ground to be 100mm min 3.6 N/mm2

All concrete blocks to be group 1 units manufactured in accordance with EN 771-3.

All masonry walls below ground to be constructed with a min M6 general purpose mortar to EN 998-2.

All masonry walls above ground to be constructed with a min M4 general purpose mortar to EN 998-2.

#### Steel Beam Schedule

**SB-1** UB 203 x 102 x 23 (S275) **SB-2** UC 152 x 152 x 23 (S275)

**SB-3** UC 152 x 152 x 23 (S275)

**SB-4** UB 178 x 102 x 19 (S275)

# Padstone Schedule

**PS-1** 330 x 100 x 140mm, 200mm bearing length **PS-2** 215 x 215 x 140mm, 200mm bearing length

**PS-3** No Padstone , 150mm bearing length

**PS-4** 215 x 100 x 65mm, 100mm bearing length

#### Timber Joist Schedule



TJ-1 38 x 195mm C24 @ 450mm C/C TJ-2 44 x 147mm C24 @ 450mm C/C

Metal strapping and noggins to be provided as per TRADA/NHBC recommendations to provide effective restraint to masonry walls.

All joists to be provided with strutting as per manufacturers details or as follows -

L < 2.5m - No strutting required 2.5m < L < 4.5m - Strutting at mid-span L > 4.5m - Strutting at third points

All roof areas to be provided with min 15mm OSB deck to provide diaphragm action. Decking to be fixed with fixings at min 150mm centres around edges of panels.

# **Timber Trimmers**

#### ......

All timber trimmers to be made from doubled up sections of adjacent timber rafters (unless noted otherwise). All built up sections to be fixed together using either M10 bolts @ 1000mm C/C's or 1/3 points if beam < 3m, or 4mm plain wire nails @ 300mm C'C/s. Fixings to be staggered.

# Triskelion Engineering Ltd

110100.

 Project Name
 Project No
 Status

 30 Abbey Road, Newstead Village
 D-23/084
 Construction

 Drawing Number
 By
 Checked
 Date


 TEL-DR-MP-01
 KS
 27/10/23

 Drawing Name
 Size
 Scale
 Rev

 Ground Floor Plan
 A3
 N/A
 C1

101 Whitaker Road, Derby, DE23 6AQ, Tel;07949168464

Structural Design Services



# **Masonry Schedule**



Below ground to be 100mm Min 7.3 N/mm2 Above ground to be 100mm min 3.6 N/mm2

All concrete blocks to be group 1 units manufactured in accordance with EN 771-3.

All masonry walls below ground to be constructed with a min M6 general purpose mortar to EN 998-2.

All masonry walls above ground to be constructed with a min M4 general purpose mortar to EN 998-2.

#### **Steel Beam Schedule**

SB-1	UB 203 x 102 x 23 (S275)
SB-2	UC 152 x 152 x 23 (S275)
SB-3	UC 152 x 152 x 23 (S275)
SB-4	UB 178 x 102 x 19 (S275)

#### **Padstone Schedule**

PS-1 330 x 100 x 140mm, 200mm bearing length
PS-2 215 x 215 x 140mm, 200mm bearing length
No Padstone , 150mm bearing length

**PS-4** 215 x 100 x 65mm, 100mm bearing length

# **Timber Joist Schedule**



**TJ-1** 38 x 195mm C24 @ 450mm C/C **TJ-2** 44 x 147mm C24 @ 450mm C/C

Metal strapping and noggins to be provided as per TRADA/NHBC recommendations to provide effective restraint to masonry walls.

All joists to be provided with strutting as per manufacturers details or as follows -

L < 2.5m - No strutting required 2.5m < L < 4.5m - Strutting at mid-span L > 4.5m - Strutting at third points

All roof areas to be provided with min 15mm OSB deck to provide diaphragm action. Decking to be fixed with fixings at min 150mm centres around edges of panels.

# **Timber Trimmers**

# .....

All timber trimmers to be made from doubled up sections of adjacent timber rafters (unless noted otherwise). All built up sections to be fixed together using either M10 bolts @ 1000mm C/C's or 1/3 points if beam < 3m, or 4mm plain wire nails @ 300mm C'C/s. Fixings to be staggered.



Notes

 Project Name
 Project No
 Status

 30 Abbey Road, Newstead Village
 D-23/084
 Construction


 Drawing Number
 By
 Checked
 Date

 TEL-DR-MP-02
 KS
 27/10/23

 Drawing Name
 Size
 Scale
 Rev

 First Floor Plan
 A3
 N/A
 C1

101 Whitaker Road, Derby, DE23 6AQ, Tel;07949168464



Bathroom

3edroom

Existing rafters are

to be retained.

# Steel Lintel Schedule

SL-1 IG L1/S 150 or similar.

All steel lintels to be provided with min 150mm end bearings and installed to manufacturers details.

# **Concrete Lintel Schedule**

#### -----

CL-1 100x140mm precast lintels.

All concrete lintels to be provided with min 150mm end bearings and installed to manufacturers details.

# Masonry Schedule



Below ground to be 100mm Min 7.3 N/mm2 Above ground to be 100mm min 3.6 N/mm2

All concrete blocks to be group 1 units manufactured in accordance with EN 771-3.

All masonry walls below ground to be constructed with a min M6 general purpose mortar to EN 998-2.

All masonry walls above ground to be constructed with a min M4 general purpose mortar to EN 998-2.

#### **Steel Beam Schedule**

**SB-1** UB 203 x 102 x 23 (S275)

**SB-2** UC 152 x 152 x 23 (S275)

**SB-3** UC 152 x 152 x 23 (S275)

**SB-4** UB 178 x 102 x 19 (S275)

# Padstone Schedule

**PS-1** 330 x 100 x 140mm, 200mm bearing length **PS-2** 215 x 215 x 140mm, 200mm bearing length

**PS-3** No Padstone , 150mm bearing length

**PS-4** 215 x 100 x 65mm, 100mm bearing length

#### **Timber Joist Schedule**



**TJ-1** 38 x 195mm C24 @ 450mm C/C **TJ-2** 44 x 147mm C24 @ 450mm C/C

Metal strapping and noggins to be provided as per TRADA/NHBC recommendations to provide effective restraint to masonry walls.

All joists to be provided with strutting as per manufacturers details or as follows -

L < 2.5m - No strutting required 2.5m < L < 4.5m - Strutting at mid-span L > 4.5m - Strutting at third points

All roof areas to be provided with min 15mm OSB deck to provide diaphragm action. Decking to be fixed with fixings at min 150mm centres around edges of panels.

# **Timber Trimmers**

# .....

All timber trimmers to be made from doubled up sections of adjacent timber rafters (unless noted otherwise). All built up sections to be fixed together using either M10 bolts @ 1000mm C/C's or 1/3 points if beam < 3m, or 4mm plain wire nails @ 300mm C'C/s. Fixings to be staggered.



Dressin

Denotes new timber stud walls

supported off top of steel SB-4

and support existing rafters.

beams. Walls are to be load bearing

RWP

Bedroom

Notes

Extg

RWP

 Project Name
 Project No
 Status

 30 Abbey Road, Newstead Village
 D-23/084
 Construction

 Drawing Number
 By
 Checked
 Date

 TEL-DR-MP-03
 KS
 27/10/23

 Drawing Name
 Size
 Scale
 Rev

 Second Floor Plan
 A3
 N/A
 C1