

The Old Rectory

The Street

Rodmell

East Sussex

ROOF TILES- METHOD

Extend scaffold to perimeter to provide access to all elevations, table lifts to all gables.

Provide temporary roof to righthand flat roof, corrugated sheeting to roof and monarflex sheeting to sides down to eaves and parapet.

Roof covering main house

Strip existing peg tiles & fittings & sort sound for re-use.

Supply & fit to existing timberwork Tyvek breathable underlay on 19 x 3 treated battens. Re-fix previously sorted sound tiles making up the deficiency with tiles to match as near as possible and used on the inside slopes . All external! slopes to be tiled with existing tiles.

Double course at eaves.

Verge bedded and pointed on slate undercloak

Existing ornamental ridge to be set aside and used on front elevation

Internal ridge to be hand made sand faced clay ridge to match the existing internal ridge.