





4 LOVER'S LANE WALL ELEVATION
1:100



1 FRONT GARDEN PAVEMENT WALL
1:100



- NOTES -
- all dimensions to be checked on site



MANSIONHOUSE ROAD

Proposed Work:

The work proposed to this C-Listed Villa is a mixture of internal remodelling, demolition, new extensions, necessary repairs and reinstatement as follows:

Ground Floor:

Carefully demolish 1950s garage and doorway to rear garden and rebuild as shown to form new garage and workshop at a lower floor level than existing. New garage to have single ply membrane roof and roof over workshop and end of garage to have sedum roof covering.

Construct new Victorian-style greenhouse onto workshop wall using recycled Victorian bricks to form dwarf wall, rear wall and wall to new tool shed adjacent. Tool shed to have recycled Scotch slate roof and cast iron rainwater goods.

Demolish existing 1980s timber sunroom and replace with Orangery by Mozolowski and Murray as shown with new slapping into former family room. Family room reinstated as main kitchen room. Former kitchen, WC and corridor reconfigured to provide accessible WC and shower, new utility space, new microrenewable plant space.

Carefully demolish existing wall, door and window between existing WC and utility space and rebuild handed. Remove modern polycarbon roof over former courtyard and reinstate courtyard as external wood and bin store with new flags, etc

Install Air Source Heat Pump to south west elevation of new accessible WC in tandem with roof mounted PV array.

Roof:

Replace existing first floor bathroom rooflight with double glazed rooflight.

Repair cementitious render to northern chimney.

Add roof hatch and install new PV array.

Introduce new hopper and downpipe at valley on rear elevation to deal with overflow issues and add new downpipes in response to new extensions, etc.

Front Garden:

Remove existing privet hedge and reinstate iron railings to street stone wall with local repairs as required.


Carefully demolish stone pier and hand driveway access, rebuilding pier and gates in new position as shown. Decrease gradient of run-in to suit new lower garage floor level. Create planted borders and new path to front entrance.

Rear Garden:


Remove current single level change and redevelop garden to levels as shown new patio at Orangery.

Block up doorway to Lover's Lane with stone on public side but leave timber door on garden side due to security risk.

2 SITE LAYOUT & ROOF PLAN
1:100



3 GARDEN SECTION & SIDE ELEVATION
1:100



ASSIST DESIGN

STATION TERRACE
34 KEAN STREET
BRIDGTON
GLASGOW G47 2DP
Tel: 0141-554 9555
Fax: 0141-554 9112
m@assistdesign.co.uk

MANSIONHOUSE
11 MARINE ST
LEITH
EDINBURGH EH6 8BB
Tel: 0131-555 5100
Fax: 0131-555 1518
m@assistdesign.co.uk

client:		Mr & Mrs Drury	
project:		33 Mansionhouse Road	
drawing title:		Proposed Site Plan/ Sectional elevation	
scale:	date:	drawn:	checked:
1:100	OCT	MF	EW
@ A1	2020		
drawing number:		revision:	
5090 L(21)02		D02	