Danygraig Road, Risca, Newport NP11 6DP

F: 01633 601280 E: bricksbm@marshalls.co.uk W: www.marshalls.co.uk/commercial

T: 01633 612671

Marble Grey Facing Bricks

Date Created: 28/01/21





Marble Grey is a blend of light and dark greys, giving a beautiful marbled appearance whilst retaining the effect of traditional brickwork. Marble Grey is part of the Contemporary Facing Brick range and has specifically been developed to offer a high quality facing brick product that is perfect for modern architecture. These bricks will look stunning in your next project and can also be used alongside other colours to allow for greater design flexibility.

DESCRIPTION	
Manufacturing Process	Vibro-compacted pressed concrete
Base Raw Material	Concrete
Green Guide	A+
CE Marking/DOP	https://www.marshalls.co.uk/dop
NBS Specification	F10/215

Date Created: 28/01/21



Marble Grey Facing Bricks

PHYSICAL PROPERTIES	
Work Dimensions (mm)	215 x 100 x 65
Nominal Dimensions (mm)	215 x 100 x 65
Durability (Freeze-thaw)	Frost Resistant
Gross Density	1920kg/m³
Thermal Conductivity (K value)	1.11 W/mK (dry); 1.24 W/mK (@3%); 1.33 W/mK (@5%)
Compressive Strength (MPa)	>22.5N. Air dry
Water Vapour Permeability	5/15µ (Tabulated from EN 1745)
Shear Bond Strength	0.15N/mm² (Tabulated from EN 998-2: 2003, Annex C)
Dimensional Stability	<0.6 mm/m

SPECIFICATION	
Selection Of Mortar	Spacing and width should be based on the guidelines provided in BS EN 1996 - Design of Masonry Structures
Emission of Asbestos	No content
Reaction to fire	Euroclass A1
Dangerous Substances	No performance declared
Movement Joints	Spacing and width should be based on the guidelines provided in BS EN 1996 - Design of Masonry Structures
Moisture Movement	<0.45mm/m

APPLICATION	
Suitability	Eminently suitable for use below dpc in foundations, boundary walls and externally above ground level up to sulphate resistance class DS2, regardless of the severity of exposure. Manufactured and tested in accordance with BS EN 771-3: 2011+A1 2015: Specification for Masonry Units:

Aggregate Concrete Masonry Units

SITE WORKS	
Installation	Avaliable on request
SUPPLY	
Packaging	Self contained packs, palletised with polythene stretch hood and with or without banding straps dependant on supply works
No. units per pack	396
FURTHER INFORMATION	J
Cleaning & Maintenance	Cleaning & maintenance details are available on request
Efflorescence	Any product containing cement during its early life may exhibit a temporary white discolouration known as efflorescence. This is not a product fault and will gradually disappear with exposure to natural weathering and trafficking. Our manufacturing process involve the incorporation of advanced additives both within and on the surface of the brick. The amount of efflorescence emanating from the bricks can thus be classed as minimal
Weathering	It should be appreciated that with all products weathering and site conditions can cause shade variation to appear across the surface of individual units. This does not in any way affect the performance of the units and any such variation will diminish over a period of time as the product matures.
Product Evolution	The evolution of new product design is continuous and information is subject to change without notice. Customers should check with the supplier to ensure that they have the latest details Marshalls reserve the right to amend the technical information as deemed necessary and in accordance with the relevant national and international standards without notice
Contact Us	As many of these products are made to

order for specific markets, please obtain further details on specification details, product availability, pack sizes and weights from your local Edenhall Sales Office, or alternatively call our Head

Office