

- Site Boundary
- Proposed vehicular asphalt to engineers specification.
- Proposed coloured pedestrian asphalt to maintenance path to engineers specification. Colour: buff
- Q25 31 Concrete flag paving system  
Manufacturer: Marshalls or similar approved.  
Product reference: Modal Paving.  
Colour: light granite and mid grey.  
BS EN 1338: 2003/ BS EN 1339: 2003
- Q25 33 Concrete paving blocks to Parking Bays and Drop off  
Manufacturer: Marshalls or similar approved  
Product: Modal priora permeable paving  
Colour: light granite and mid grey.  
BS EN 1338: 2003/ BS EN 1339: 2003
- Q23 225 Silver grey resin bound gravel  
Manufacturer: Addagrip Terraco or similar approved  
Colour: Lucerne Silver  
Build up: To engineers detail
- Q23 225 Buff resin bound gravel  
Manufacturer: Addagrip Terraco or similar approved  
Colour: Dorset Gold  
Build up: To engineers detail
- Q26 230 Wet pour surfacing to Therapy Garden Sports Area  
Supplier: Abacus Playgrounds  
Product: Wet pour surfacing  
Colour: Dark Green
- Reinforced grass for fire access  
Bodpave
- Q25 54 Tactile paving for pedestrian crossings into a road
- Q25 55 Hazard warning paving to top and base of steps
- L37 310 Steps outside plant room  
Marshalls precast concrete step unit 1000 x 400 x 150mm  
colour: silver grey  
Handrail to steps: L37 151 in stainless steel
- Existing woodland to be retained
- Q30 310 Proposed Grass Seed to Visual Amenity Gardens  
Mixture: Germinal Amenity A24 Wear and Tear
- Q30 312 Wildflower Seed Mixture  
Supplier: Emorsgate Seeds  
Mixture: EM3F
- Ornamental planting  
REFER TO PLANTING PLANS
- Proposed tree planting
- Existing tree retained
- Existing tree removed
- Existing woodland to be removed
- Q40 126A Proposed open mesh steel panel security fencing 2.4m with gates  
Manufacturer: CLD fencing  
Reference: CLD Securus SR1 High Security  
Colour: RAL 6005 Green  
Submit manufacturer's and installer's certificates, to BS 1722-14.
- Q40 126 Proposed open mesh steel panel security fencing 4.2m assessment room gardens, Section 136 and Seclusion garden  
Manufacturer: CLD Fencing  
Reference: CLD Securus SR1 High Security  
Antigliare fencing  
Colour: RAL 6005 Green  
Conformity: Submit manufacturer's and installer's certificates, to BS 1722-14.
- Q40 210 Wooden post and rail fencing  
Manufacturer: Contractor's choice  
Height: 1.4m high  
To provide a 30-year service life.  
Conformity: Submit manufacturer's and installer's certificates, to BS 1722-7.
- Q40 210A Timber Knee Rail  
Manufacturer: Jackson Fencing or equal.  
Product reference: Diamond Wood Rail Fence.  
Height: 900mm  
Dimensions: 100 x 100mm section, posts at 1350mm centres.  
Material: Jakcure treated softwood.  
Finish: Planed finish.

- L37 150 Handrail to external ramp
- Q50 190 Proposed bollards  
Manufacturer: Marshalls or similar approved  
Product reference: Rhino Guard PAS 170  
Material: 316 Stainless steel, bead blasted  
Finish: as manufactured  
Size: 800mm height, 140mm diameter
- Q50 209 & Q25 31 Bin Compound and paving system  
Manufacturer: Langley Design or similar approved  
Product reference: Sheldon bin store SBS303  
Type: Enclosed bin compound with roof  
Steel structure: galvanised  
Timber: treated redwood  
Roof: 16mm multiwall polycarbonate roofing system  
Finish: as manufactured  
Size: Bespoke size to suit bin units  
6445mm x 3500mm x 2600mm (h)
- Q50 211 & Q25 31 Proposed secured cycle shelter, cycle hoops and paving system.  
Manufacturer: Langley Design or similar approved  
Product reference: Sheldon cycle shelter SCS310  
Type: Semi enclosed cycle parking compound.  
Three sides clad in timber  
Steel structure: galvanised  
Timber: treated redwood  
Finish: as manufactured  
Size: Bespoke size to suit number of cycle spaces  
4000mm x 3100mm x 2600mm (h)  
Capacity: 3 cycle hoops to hold 4 bikes
- Q50 210 Proposed cycle hoops within secured cycle shelter.  
Manufacturer: Marshalls  
Product reference: Geo cycle stand  
Type: Single stands  
Material: Stainless steel 316
- Q50 220 Benches within Public and Entrance Spaces  
Manufacturer: Artform Urban Furniture or similar approved.  
Product reference: MultiplCITY bench  
Length: Varies
- Q50 221 Looped Benches Within Courtyards  
Manufacturer: Artform Urban Furniture or similar approved.  
Product reference: Loop  
Material: Polyethylene  
Size: 1800mm diameter  
Colour Blue  
Finish: Textured
- Q50 222 Straight Benches within Courtyards  
Manufacturer: Artform Urban Furniture or similar approved.  
Product reference: Loop Line  
Length: 2000mm  
Material: Polyethylene  
Colour: Green  
Finish: Textured
- Q50 223 Curved Benches within Courtyards  
Manufacturer: Artform Urban Furniture or similar approved.  
Product reference: Loop Arc  
Length: 2015mm  
Material: Polyethylene  
Colour: Green  
Finish: Textured
- Q50 225 Seating within Courtyards  
Manufacturer: Artform Urban Furniture or similar approved.  
Product reference: HopOp 500  
Dimensions: 500mmx400mm  
Material: Polyethylene  
Colour Light Blue  
Finish: Textured
- Q50 226 Continuous bench to Therapies Garden  
Manufacturer: Artform Urban Furniture or similar approved.  
Product reference: Cobra Bench  
Dimensions: 453mm high, 493mm deep, 2193 module length  
Overall length: 23.6m  
Material: Timber top and steel support  
Finish: Treated hardwood and steel powder coated RAL 7012
- Q50 230 Tables Within Courtyards  
Manufacturer: Artform Urban Furniture or similar approved.  
Product reference: Loop Table  
Material: Polyethylene  
Size: 1130mm diameter  
Colour Blue  
Finish: Textured
- Q50 231 Table Tennis  
Manufacturer: Cornilleau or similar approved.  
Product reference: Cornilleau 510 Table  
Size: Bed 153cm x 275cm. Surface 7mm resin laminate  
Height: 77cm.  
Colour: Blue.



- Q50 232 Table within Seclusion & De-escalation gardens  
Manufacturer: Artform Urban Furniture or similar approved.  
Product reference: Air L-A-C Table  
Size: 2200mm length, 1660mm wide, 444mm / 744mm tall  
Material: Timber top and steel support  
Q50 240 Litter bins to public areas  
Manufacturer: Artform Urban Furnitured  
Product reference: Box (100L)  
Material: Steel  
Colour and Finish: Galvanized and polyester powder coated RAL 7012
- Q50 250 Fitness Equipment  
Manufacturer: Broxap or similar approved  
Product reference: Sunshine Gym  
Material: Steel  
Finish: Galvanized and polyester powder coated  
Note: Total number and Equipment to be confirmed with Trust.
- Q31 292 Prefabricated plant containers  
Manufacturer: Euro Planters  
Height: 1m  
Product reference: Bespoke item  
Material: GRP and timber  
Colour: GRP planter to be RAL 7016 Anthracite grey
- Q31 292 Timber Benches as part of planter  
Manufacturer: Euro Planters  
Height: 450mm above FGL  
Product reference: Bespoke item  
Material: Timber

- Q31 298 Timber plant planters  
Manufacturer: Taylor Made Planters or equivalent  
Product: Wooden Vegetable Planters with raised legs  
Size: 1000 x 1000 x 500mm;  
1000 x 500 x 500mm;  
1500 x 1000 x 500mm  
Material/Finish: Natural finish  
To BS EN 942
- Geogrow retaining structure. Details by Geogrow specialist
- Proposed external retaining wall
- Proposed sail canopy  
Canopies to be on posts  
Details by others
- Suggested location of muster point to be reviewed and agreed

Courtyard gardens to have allowance for external taps.



The use of this data by the recipient acts as an agreement of the following statements. Do not use this data if you do not agree with any of the following statements:  
Ryder Architecture has co-ordinated relevant information received from third parties, but are not responsible for the content of the information received from others.  
The controlled version of this drawing should be viewed in DWG or PDF format not DWG or other formats. All prints of this drawing must be made in full colour.  
Where this drawing has been based upon Ordnance Survey data, it has been reproduced under the terms of Ryder Licence No. 100000144. Reproduction of this drawing in whole or in part is prohibited without the prior permission of Ordnance Survey.  
Do not scale the drawing. Use figured dimensions in all cases. Check all dimensions on site. Report any discrepancies in writing to Ryder before proceeding.



Rev	Description	Drawn	Checked	Date
C5	Updates made following comments received from Vinci on 8.12.23	ADL	ADL	14/12/23
C4	Retaining walls to the east and south omitted and replaced with a Geogrow structure. Position of post and rail fence amended to suit location of Geogrow structure. Layout of maintenance path to the east revised to suit position of Geogrow. Double gate added to Acute garden. External furniture raised planters for acute gardens revised to facilitate drainage. Removal of existing gas house and timber. Tactile paving indicate for crossings. Levels along eastern boundary revised to suit geogrow structure. Artificial grass omitted. Levels, external furniture and softscape on courtyards revised to allow drainage into proposed gullies, surface for courtyard confirmed by IHP to be not permeable.	ADL	ADL	24/10/23
C3	Fence specification updated as advised by IHP	ADL	ADL	13/12/22
C2	Issued for Stage 5, additional labels and notes added to drawings.	TJ	MG	26/10/22
C1	Issued for Stage 5	TJ	CS	07/10/22
P1	Fire tender access updated to show 4.1m width and reduced turning length	ADL	KPE	16/08/22
P1	ToW levels for retaining wall near fire access indicated	ADL	KPE	26/07/22
P1	Mewp access amended, retaining walls to south revised	ADL	KPE	13/07/22
P9	Revision clouds omitted	ADL	KPE	11/07/22
P8	Areas in rev. clouds highlight changes since Nov planning submission	ADL	KPE	09/06/22
P7	Issued to Curtris to assist with IFS information	ADL	KPE	26/05/22
P6	Issued for Costing	KPE	ADL	20/01/22
P5	Issued for Costing	KPE	ADL	20/12/21
P4	Issued for Planning	KPE	ADL	25/11/21
P3	Site plan updates following review from wider design team, issued for planning	KPE	ADL	18/11/21
P2	Site plan updates, issued for review	KPE	ADL	15/11/21
P1	First issue, draft for comments	KPE	ADL	09/11/21

Project ID	Originator	Zone	Level	Type	Role	Number
RG0004	- RYD	- ZZ	- XX	- DR	- L	- 2100
Project Number	Scale at	Status	Revision			
10443-00	1 : 500	S4	C5	.0		