



Roman Road

High Park Road

Gate

Bramble and Himalayan Honeysuckle to be removed by hand adjacent to north and east boundary fences. New shrubs and small trees to be planted informally for seclusion using native species such as: Holly, Hawthorn, Yew, Gorse, Hazel.

Desirable tree saplings & shrubs include:
Scots Pine - *Pinus sylvestris*
English Oak - *Quercus robur*
Beech - *Fagus sylvatica*
Rowan - *Sorbus aucuparia*
Hornbeam - *Carpinus betulus*
Hawthorn - *Crataegus monogyna*
Silver Birch - *Betula pendula*
Sweet Chestnut - *Castanea sativa*
Heather - *Calluna vulgaris*
Gorse - *Ulex europaeus*
Broom - *Cytisus scoparius*

Undesirable tree saplings & shrubs include:
Holm Oak - *Quercus ilex*
Rhododendron - *Rhododendron sp.*
Cherry Laurel - *Prunus laurocerasus*
Photinia - *Photinia sp.*
Cotoneaster - *Cotoneaster sp.*
Laurastinus - *Viburnum tinus*
Strawberry Tree - *Arbutus unedo*

For areas inside and outside of the proposed glades and paths: **Undesirable tree & shrub saplings** to be removed by hand

Lift desirable tree saplings within the proposed glades & paths and replant elsewhere on site. After transplanting saplings, the glades and paths are to be maintained by mowing or rolling **inside the dashed red line only**

Lift desirable tree saplings within the proposed glades & paths and replant elsewhere on site. After transplanting saplings, the glades and paths are to be maintained by mowing or rolling **inside the dashed red line only**

Paths to be max. 1 metre wide

For areas outside the glades and paths: **No desirable tree & shrub saplings** are to be removed or damaged.

Bracken to be carefully beaten annually and Bramble to be carefully cut biennially without damage to **desirable tree and shrub saplings**

Periodically trim back lateral spread of evergreen shrubs (every 2 years) to prevent excessive encroachment into site

Retain evergreen boundary shrubs for screening / seclusion

Remove one small Cotoneaster (581b) for access path. **No digging into bund**

Soft Verge

Bund

Bund

Bund

Chain Link Fence

Close Board Fence

Close Board Fence

Retain all evergreen boundary shrubs for screening / seclusion

53 Roman Road

APPENDIX C

SITE PLAN - SUMMARY OF MANAGEMENT PROPOSALS

PLAN NOT TO SCALE
The plan is not topographical. The tree positions have been plotted by eye. The tree location plan is fit for a TPO application but does not comply with BS.5837 and must not be used for development purposes