






Location Plan
Scale 1:1250



Location Plan
Scale 1:500



Office: Ash 3-4 Centrix House,
Newton Le Willows,
WA12 9UY

Telephone: +44 (0) 1625 326 777
Website: sales@granadahome.com

Client:

The Extension Guys
Ash 3-4 Centrix House,
Newton Le Willows WA12 9UY

Project / Title:

Proposed Single Storey Side
Extension at 8 Bridle Way, Woodford,
Stockport, SK7 1QL

AutoCAD Location

D:\BentleyP&PM\Planning Apps\


Drawn: MJD

Scale: As Shown @ A3

Date: 12.10.23


No. SSRE-8BW-001

Rev. A



Existing Ground Floor Layout

Scale 1:50



Office: Ash 3-4 Centrix House, Newton Le Willows, WA12 9UY
 Telephone: +44 (0) 1625 326 777
 Website: www.theextensionguys.co.uk

Client: The Extension Guys, Ash 3-4 Centrix House, Newton Le Willows WA12 9UY

Project / Title: Proposed Single Storey Rear Extension at 8 Bridle Way, Woodford, Stockport, SK7 1QL

AutoCAD Location: D:\BentleyP&PM\Planning Apps\
 Drawn: MJD Scale: As Shown @ A3 Date: 12.10.23

No. SSEE-8BW-002




Existing Front Elevation
Scale 1:100




Existing Rear Elevation
Scale 1:100



Existing Side Elevation
Scale 1:100



Existing Side Elevation
Scale 1:100



Office: Ash 3-4 Centrix House,
Newton Le Willows,
WA12 9UY

Telephone: +44 (0) 1625 326 777
Website: sales@granadahome.com


Client:
The Extension Guys
Ash 3-4 Centrix House,
Newton Le Willows WA12 9UY

AutoCAD Location: D:\BentleyP&PM\Planning Apps\
Drawn: MJD | Scale: As Shown @ A3 | Date: 12.10.23


Project / Title:
**Proposed Single Storey Side
Extension at 8 Bridle Way, Woodford,
Stockport, SK7 1QL**

No. SSRE-8BW-003

Rev. A



Proposed Ground Floor Layout
Scale 1:50



Office: Ash 3-4 Centrix House,
Newton Le Willows,
WA12 9UY

Telephone: +44 (0) 1625 326 777
Website: www.theextensionguys.co.uk

Client: The Extension Guys, Ash 3-4 Centrix House, Newton Le Willows WA12 9UY

Project / Title: Proposed Single Storey Rear Extension at
8 Bridle Way, Woodford, Stockport, SK7 1QL


AutoCAD Location D:\BentleyP&M\Planning Apps\

Drawn: MJD Scale: As Shown @ A3 Date: 12.10.23

No. SSEE-8BW-004




Proposed Front Elevation
Scale 1:100




Proposed Rear Elevation
Scale 1:100



Proposed Side Elevation
Scale 1:100



Proposed Side Elevation
Scale 1:100



Office: Ash 3-4 Centrix House,
Newton Le Willows,
WA12 9UY

Telephone: +44 (0) 1625 326 777
Website: sales@granadahome.com

Client:
The Extension Guys
Ash 3-4 Centrix House,
Newton Le Willows WA12 9UY

AutoCAD Location: D:\BentleyP&PM\Planning Apps\
Drawn: MJD | Scale: As Shown @ A3 | Date: 12.10.23

Project / Title:
**Proposed Single Storey Side
Extension at 8 Bridle Way, Woodford,
Stockport, SK7 1QL**

No. SSRE-8BW-005

Rev. A

BUILDING REGULATIONS NOTES

PLANNING NOTE - The local Planning department to be consulted on any local requirements relating to Planning Permissions and Permitted Development rights. An Article 4, which removes certain rights, may be in place. Prior approval to be sought where required.

SINGLE-STOREY EXTENSION

An extension or addition to your house is considered to be permitted development, not requiring an application for planning permission, provided certain limits and conditions are met.

1. On designated land* - no cladding of the exterior. *Designated land (Article 2(3)) includes national parks and the Broads, Areas of Outstanding Natural Beauty, conservation areas and World Heritage Sites.
 2. On designated land* - no side extensions. Rear extension - No permitted development for rear extensions of more than one storey. The regime for larger single-storey rear extensions (see point 9) does NOT apply to houses on designated land.
 3. No more than half the area of land around the "original house" would be covered by additions or other buildings. Sheds and other outbuildings must be included when calculating the 50 per cent limit.
 4. No extension forward of the principal elevation or side elevation fronting a highway.
 5. Materials to be similar in appearance to the existing house.
 6. Side extensions to be single storey. Width of side extension must not have a width greater than half the width of the original house.
 7. Side extensions to have a maximum height of four metres and width no more than half that of the original house.
 8. If the extension is within 2m of a boundary, maximum eaves height should be no higher than 3m to be permitted development.
 9. Single-storey rear extensions must not extend beyond the rear wall of the original house by more than 4m if a detached house; or more than 3m for any other house. Where not on designated land (Article 2(3)) or a Site of Special Scientific Interest, this limit is increased to 8m if a detached house; or 6m for any other house.
 10. Maximum height of a single-storey rear extension of 4m. (or less than 3m if within 2m of a property boundary)
- . Maximum eaves and ridge height of extension no higher than existing house.

CDM REGULATIONS 2015

The client must abide by the Construction Design and Management Regulations 2015. The Client must appoint a Contractor, if more than one Contractor is to be involved, the Client will need to appoint (in writing) a Principal Designer (to plan, manage and coordinate the planning and design work), and a Principal Contractor (to plan, manage and coordinate the construction and ensure there are arrangements in place for managing and organising the project).

Domestic Clients

The Domestic Client is to appoint a Principal Designer and a Principal Contractor when there is more than one Contractor, if not your duties will automatically be transferred to the Contractor or Principal Contractor.

The Designer can take on the duties, provided there is a written agreement between you and the Designer to do so.

The Health and Safety Executive is to be notified as soon as possible before construction work starts if the works:

- (a) Last longer than 30 working days and has more than 20 workers working simultaneously at any point in the project.
Or:
(b) Exceeds 500 person days.

PARTY WALL ACT

The owner, should they need to do so under the requirements of the Party Wall Act 1996, has a duty to serve a Party Structure Notice on any adjoining owner if building work on or near an existing Party Wall involves any of the following:

- Support of beam
- Insertion of DPC through wall
- Raising a wall or cutting off projections
- Demolition and rebuilding
- Underpinning
- Insertion of lead flashings
- Excavations within 3 metres of an existing structure where the new foundations will go deeper than adjoining foundations, or within 6 metres of an existing structure where the new foundations are within a 45 degree line of the adjoining foundations.

A Party Wall Agreement is to be in place prior to start of works on site.

THERMAL BRIDGING

Care shall be taken to limit the occurrence of thermal bridging in the insulation layers caused by gaps within the thermal element, (i.e. around windows and door openings). Reasonable provision shall also be made to ensure the extension is constructed to minimise unwanted air leakage through the new building fabric.

MATERIALS AND WORKMANSHIP

All works are to be carried out in a workmanlike manner. All materials and workmanship must comply with Regulation 7 of the Building Regulations, all relevant British Standards, European Standards, Agreement Certificates, Product Certification of Schemes (Kite Marks) etc. Products conforming to a European technical standard or harmonised European product should have a CE marking.

SITE PREPARATION

Ground to be prepared for new works by removing all unsuitable material, vegetable matter and tree or shrub roots to a suitable depth to prevent future growth. Seal up, cap off, disconnect and remove existing redundant services as necessary. Reasonable precautions must also be taken to avoid danger to health and safety caused by contaminants and ground gases, e.g. landfill gases, radon, vapours etc. on or in the ground covered, or to be covered by the building.

EXISTING STRUCTURE

Existing structure including foundations, beams, walls and lintels carrying new and altered loads are to be exposed and checked for adequacy prior to commencement of work and as required by the Building Control Officer.

LINTELS

- For uniformly distributed loads and standard 2 storey domestic loadings only
Lintel widths are to be equal to wall thickness. All lintels over 750mm sized internal door openings to be 65mm deep pre-stressed concrete plank lintels. 150mm deep lintels are to be used for 900mm sized internal door openings. Lintels to have a minimum bearing of 150mm on each end. Any existing lintels carrying additional loads are to be exposed for inspection at commencement of work on site. All pre-stressed concrete lintels to be designed and manufactured in accordance with BS EN 1992-1-1, with a concrete strength of 50 or 40 N/mm² and incorporating steel strands to BS 5896 to support loadings assessed to BS 5977 Part 1.
For other structural openings provide proprietary insulated steel lintels suitable for spans and loadings in compliance with Approved Document A and lintel manufacturer's standard tables. Stop ends, DPC trays and weep holes to be provided above all externally located lintels.
Independent lintels to have an insulated cavity closure between the inner and outer lintel.

FLAT ROOF RESTRAINT

100m x 50mm C16 grade timber wall plates to be strapped to walls using 1200mm x 30mm x 5mm galvanised mild steel straps at maximum 2.0m centres, straps to be fixed to internal wall faces.

OPENINGS AND RETURNS

An opening or recess greater than 0.1m² shall be at least 550mm from the supported wall (measured internally).

STRIP FOUNDATION


Provide 225mm x 600mm concrete foundation, concrete mix to conform to BS EN 206:2013 and BS 8500-2. All foundations to be a minimum of 1000mm below ground level, exact depth to be agreed on site with Building Control Officer to suit site conditions. All constructed in accordance with 2010 Building Regulations A1/2 and BS 8004:2015 Code of Practice for Foundations. Ensure foundations are constructed below invert level of any adjacent drains. Base of foundations supporting internal walls to be min 600mm below ground level. Sulphate resistant cement to be used if required. Please note that should any adverse soil conditions be found or any major tree roots in excavations, the Building Control Officer is to be contacted and the advice of a Structural Engineer should be sought.

PIPES PASSING THROUGH WALLS

Walls above pipes passing through substructure walls to be supported on suitable lintel on semi-engineering bricks. Pipe to be provided with a 50mm clearance all round, opening to be masked with granular backfill (pea shingle) around pipe. DPC to be provided as required by BCO.

Alternatively

Where new pipework passes through external walls the pipe work is to be provided with 'rocker pipes' at a distance of 150mm either side of the wall face. The 'rocker pipes' must have flexible joints and be a maximum length of 600mm.

 <p>Office: Ash 3-4 Centrix House, Newton Le Willows, WA12 9UY</p> <p>Telephone: +44 (0) 1625 326 777 Website: sales@granadahome.com</p>	Client:	The Extension Guys Ash 3-4 Centrix House, Newton Le Willows WA12 9UY	Project / Title:	Proposed Single Storey Side Extension at 8 Bridle Way, Woodford, Stockport, SK7 1QL
	AutoCAD Location	D:\BentleyP&PM\Planning Apps\	No.	SSRE-8BW-006
	Drawn: MJD	Scale: As Shown @ A3 Date: 12.10.23		

TIMBER SUSPENDED FLOOR

To meet min U value required of 0.18 W/m²K - P/A ratio 0.5

gk not more than 0.5

Ground preparation -Remove top soil and vegetation, apply total weed killer and 150mm min thick sand blinded hardcore, then either –

(i) Provide concrete ground cover of at least 100mm thick or

(ii) Prepare the ground to an even surface and lay a ground cover of concrete at least 50mm thick, on a damp-proof membrane of at least 1200 gauge polyethylene, laid on a bed of fine blinding material.

Floor construction - min 20mm tongue and groove softwood boards or moisture resistant particle/chipboard grade type C4 to BS EN 312:2010 as required. Lay with staggered joints on 47mm x 145mm C24 grade soft wood joists at maximum 400mm centres, max span 3.21m. Joists to be supported off proprietary galvanized joist hangers built into new masonry walls or fixed to treated timber wall plates resin bolted to walls at 600mm centres. If required, floor joists also to be supported on 100mm x 50mm treated wall plates and DPC fixed to masonry honeycombed sleeper walls built on thickened oversite concrete or foundation, as required by BCO.

Joists to be infilled with 130mm Kingspan Kooltherm insulation between joists fixed with proprietary clips.

The top surface of the ground cover under the building shall be above the finished level of the adjoining ground. The underside of the floor joists not to be less than 150mm above the top of the ground cover. The underside of any wall plate not to be less than 75mm above the top of the ground cover.

Ventilation of Floor

Provide cross-ventilation under floor to outside air by ventilators in at least 2 opposite external walls of the building. Ventilation openings having an opening area of 1500mm² per metre run of perimeter wall or 500mm² per square metre of floor area whichever gives the greater opening area. All sleeper walls or similar under floor obstructions shall be of honeycombed construction or have similar provision for distribution of ventilation. The under floor space shall be free from debris. Ducts to be sealed using gas proof tap if they pass through the radon barrier.

WALLS BELOW GROUND

All new walls below ground to be constructed using blockwork compliant with BS EN 771 and suitable for below ground level or semi engineering brickwork. Walls to be built using 1:4 masonry mortar mix or equal approved specification to BS EN 1996-1-1. Cavities below ground level to be filled with lean mix concrete min 225mm below damp proof course. Or provide lean mix backfill at base of cavity wall (150mm below damp course) laid to fall to weepholes.

TIMBER FRAME WALL

To achieve minimum U Value of 0.18 W/m²K

Timber cladding fixed to 25 x 38mm preservative-treated battens (provide counter battens to ensure vented and drained cavity if required) fixed to breathable membrane (having a vapour resistance of not more than 0.6 MNs/g) and 12mm thick WBP external quality plywood sheathing (or other approved). Ply fixed to treated timber frame studs constructed using: 150mm x 50mm head & sole plates and vertical studs (with noggins) at 400mm ctrs or to s/engineer's details & calculations. Insulation to be 120mm Celotex XR4000 between studs with 25mm Celotex TB4000 over. Provide vcl and 12.5mm plasterboard over internal face of insulation. Finish with 3mm skim coat of finishing plaster. All junctions to have water tight construction, seal all perimeter joints with tape internally and with silicon sealant externally.

Walls within 1m of the boundary to be lined externally with 12.5mm Supalux and 12.5mm Gyproc FireLine board internally to achieve 1/2 hour fire resistance from both sides and timber cladding to be treated with Fire Retardant Coating for Timber (ESVFR & QVFR) or similar paint system to achieve class 0 and 1 EU SBI/B/s1/d0.

DPC

Provide horizontal strip polymer (hyload) damp proof course to both internal and external skins, DPC to be placed a minimum 150mm above external ground level. New DPC to be made continuous with existing DPC's and with floor DPM. Vertical DPC to be installed at all reveals where cavity is closed.

WALL TIES

All walls constructed using stainless steel vertical twist type retaining wall ties built in at 750mm ctrs horizontally, 450mm vertically and 225mm ctrs at reveals and corners in staggered rows. Wall ties to be suitable for cavity width and in accordance with BS EN 84.

Wall ties for cavities over 150mm to be suitable for cavity width, and installed as manufacturer's details.

CAVITIES

Provide cavity trays over openings and where roofs abut walls. All cavities to be closed at eaves and around openings using Thermabate or similar non combustible insulated cavity closers. Provide vertical DPCs around openings and abutments. All cavity trays must have 150mm upstands and suitable cavity weep holes (min 2) at max 900mm centres.

CAVITY BARRIERS

30 minute fire resistant cavity barriers to be provided around openings, at tops of walls, gable end walls, vertically at junctions with separating walls and horizontally at separating floors. Cavity trays to be provided over barriers where required. Trays and cavity barriers to be installed according to manufacturer's details.

WARM FLAT ROOF

(imposed load max 1.0 kN/m² - dead load max 0.75 kN/m²)

To achieve U value 0.15 W/m²K

Flat roof covering to be glass reinforced plastic (GRP) system with aa fire rating and a current BBA or other approved accreditation be laid in compliance with manufacturers details by flat roofing specialist, onto 22mm exterior quality plywood over 150mm Celotex XR4000 on sw firings to minimum 1 in 40 fall on sw treated 47 x 195mm C24 flat roof joists at 400mm ctrs to give a max span of 4.51m or as Structural Engineer's details and calculations. Fix 12.5mm plasterboard over vapour barrier to underside of joists, finish a with plaster skim. Provide cavity tray to where new roof abuts existing house.

Provide restraint to flat roof by fixing of 30 x 5 x 1200mm ms galvanised lateral restraint straps at maximum 2000mm centres fixed to 100 x 50mm wall plates and anchored to wall.

LEAD WORK AND FLASHINGS

All lead flashings, any valleys or soakers to be Code 5 lead and laid in accordance with BS 5534 and BS EN 12588. Flashings to be provided to all jambs and below window openings with welded upstands. Joints to be lapped min 150mm and lead to be dressed 200mm under tiles, etc.

INTERNAL STUD PARTITIONS

100mm x 50mm softwood treated timbers studs at 400mm ctrs with 50 x 100mm head and sole plates and solid intermediate horizontal noggins at 1/3 height or 450mm c/cs. Provide min 10kg/m³ density acoustic soundproof quilt tightly packed (e.g.100mm Rockwool or Isowool mineral fibre sound insulation) in all voids the full depth of the stud. Partitions to be built off doubled up joists where partitions run parallel or provide noggins where at right angles, or to be built off DPC on thickened concrete slab if solid ground floor. Walls faced throughout with 12.5mm plasterboard with skim plaster finish. Plasterboard to be taped and jointed complete with beads and stops.

ELECTRICAL

All electrical work required to meet the requirements of Part P (electrical safety) must be designed, installed, inspected and tested by a Competent Person registered under a Competent Person Self Certification Scheme such as BRE certification Ltd, BSI, NICEIC Certification Services or Zurich Ltd. An appropriate BS7671 Electrical Installation Certificate is to be issued for the work by a person competent to do so. A copy of a certificate will be given to Building Control on completion.

INTERNAL LIGHTING

Install low energy light fittings that only take lamps having a luminous efficiency better than 80 lumens per circuit watt. All fixed to have lighting capacity (lm) 185 x total floor area, to comply with Part L of the current Building Regulations and the Domestic Building Services Compliance Guide.

HEATING

Extend all heating and hot water services from existing and provide new TRVs to radiators. Heating system to be designed, installed, tested and fully certified by a GAS SAFE registered specialist. All work to be in accordance with the Local Water Authorities bye laws, the Gas Safety (Installation and Use) Regulations 1998 and IEE Regulations.

The energy performance of the new components to be assessed. The results should be recorded and given to the building owner.

All accessible pipes to be insulated to the standards in Table 4.4 Approved Document L.

SMOKE DETECTION

Mains operated linked smoke alarm detection system to BS EN 14604 and BS 5839-6:2019 to at least a Grade D category LD3 standard to be mains powered with battery back up to be installed. At least one smoke detector to be provided in each hallway and landing. In hallways exceeding 7.5m in length, no point within the hallway should exceed 7.5m from the nearest detector and no bedroom door should be further than 3m from the nearest smoke alarm. If ceiling mounted they should be 300mm from the walls and light fittings. Where the kitchen area is not separated from the stairway or circulation space by a door, there should be an interlinked heat detector in the kitchen.


ESCAPE WINDOWS

Provide emergency egress windows to any newly created first floor habitable rooms and ground floor inner rooms.

The window should have an unobstructed clear openable area that is at least 0.33m² and have no clear dimension less than 450mm high or 450mm wide.

The bottom of the openable area should be not more than 1100mm above the floor.

The window should enable the person to reach a place free from danger from fire.

 <p>Office: Ash 3-4 Centrix House, Newton Le Willows, WA12 9UY</p> <p>Telephone: +44 (0) 1625 326 777 Website: sales@granadahome.com</p>	Client:		The Extension Guys Ash 3-4 Centrix House, Newton Le Willows WA12 9UY		Project / Title:		Proposed Single Storey Side Extension at 8 Bridle Way, Woodford, Stockport, SK7 1QL	
	AutoCAD Location	D:\BentleyP&PM\Planning Apps\						
	Drawn: MJD	Scale: As Shown @ A3	Date:	12.10.23		No. SSRE-8BW-007		Rev. A

SAFETY GLAZING

All glazing in critical locations to be toughened or laminated safety glass to BS 6206, BS EN 14179 or BS EN ISO 12543-1 and Part K of the current Building Regulations, i.e. within 1500mm above floor level in doors and side panels within 300mm of door opening and within 800mm above floor level in windows.

NEW AND REPLACEMENT WINDOWS

New and replacement windows to be double glazed with 16-20mm argon gap and soft coat low-E glass. Window Energy Rating to be Band B or better and to achieve U-value of 1.4 W/m²K. The door and window openings should be limited to 25% of the extension floor area plus the area of any existing openings covered by the extension.

Insulated plasterboard to be used in reveals to abut jambs and to be considered within reveal soffits. Fully insulated and continuous cavity closers to be used around reveals.

Windows and door frames to be taped to surrounding openings using air sealing tape.

Windows to be fitted with trickle vents to provide adequate background ventilation in accordance with Approved Document F.

NEW AND REPLACEMENT DOORS

New and replacement doors to achieve a U-Value of 1.4W/m²K. Glazed areas to be double glazed with 16-20mm argon gap and soft low-E glass. Glass to be toughened or laminated safety glass to BS 6206, BS EN 14179 or BS EN ISO 12543-1 and Part K of the current Building Regulations.

Insulated plasterboard to be used in reveals to abut jambs and to be considered within reveal soffits. Fully insulated and continuous cavity closers to be used around reveals.

Windows and door frames to be taped to surrounding openings using air sealing tape.

EXTRACT TO UTILITY ROOM

To utility room provide mechanical ventilation ducted to external air capable of extracting at a rate of 30 l/s. Internal doors should be provided with a 10mm gap below the door to aid air circulation. Ventilation provision in accordance with the Domestic Ventilation Compliance Guide. Intermittent extract fans to BS EN 13141-4. All fixed mechanical ventilation systems, where they can be tested and adjusted, shall be commissioned and a commissioning notice given to the Building Control Body.

PURGE VENTILATION

Minimum total area of opening in accordance with Table 1.4 Approved Document F1.

Hinged or pivot windows with an opening angle of 15 to 30 degrees to have an openable area in excess 1/10 of the floor area of the room.

External doors and sash, hinged or pivot windows with an opening angle of equal to or greater than 30 degrees to have an openable area in excess of 1/20 of the floor area of the room.

Purge ventilation should be capable of extracting at least 4 air changes per hour per room directly to the outside.

Internal doors should be provided with a 10mm gap below the door to aid air circulation.


FLAT ROOF VENTILATION

Cross-ventilation to be provided on opposing sides by a proprietary eaves ventilation strip equivalent to 25mm continuous with fly proof screen. Flat roof insulation is to be continuous with the wall insulation but stopped back to allow a 50mm air gap above the insulation for ventilation.

C2. CONDENSATION


Walls, floors and roof of the building to be designed and constructed so that their structural and thermal performance will not be adversely affected by interstitial condensation, surface condensation or mould growth. Account to be taken of the building's form and orientation in relation to topography, prevailing winds, sunlight and over-shadowing, and the rate at which humidity is generated. Materials with the highest vapour resistance should be located on the warm side of a thermal element. VCLs to be provided where necessary.


The junctions between elements are designed to Accredited Construction Details or guidance of BRE IP17/01] and BS 5250:2021 Management of moisture in buildings to be followed.




Typical Foundation Detail

Scale 1:100


 <p>Office: Ash 3-4 Centrix House, Newton Le Willows, WA12 9UY</p> <p>Telephone: +44 (0) 1625 326 777 Website: sales@granadahome.com</p>	<p>Client:</p> <p style="text-align: center;">The Extension Guys Ash 3-4 Centrix House, Newton Le Willows WA12 9UY</p>		<p>Project / Title:</p> <p style="text-align: center;">Proposed Single Storey Side Extension at 8 Bridle Way, Woodford, Stockport, SK7 1QL</p>	
	AutoCAD Location	D:\BentleyP&PM\Planning Apps\		
	Drawn: MJD	Scale: As Shown @ A3	Date: 12.10.23	<p>No. SSRE-8BW-008</p>
				<p>Rev. A</p>



Typical Suspended Floor Detail
Scale 1:100



Typical Roof Detail
Scale 1:100



Typical Timber Clad Wall Detail
Scale 1:100



Office: Ash 3-4 Centrix House,
Newton Le Willows,
WA12 9UY
Telephone: +44 (0) 1625 326 777
Website: sales@granadahome.com

Client:
The Extension Guys
Ash 3-4 Centrix House,
Newton Le Willows WA12 9UY

Project / Title:
**Proposed Single Storey Side
Extension at 8 Bridle Way, Woodford,
Stockport, SK7 1QL**

AutoCAD Location: D:\BentleyP&PM\Planning Apps\
Drawn: MJD | Scale: As Shown @ A3 | Date: 12.10.23

No. SSRE-8BW-009

Rev. A