

*The
Palladio
Door Collection*

Edition 7

*With the new
Avant Garde
Collection*

A fine example of our satinized glass for doors and sidelights. This product is produced in-house and is quite unique in its crystal-like appearance as is evident in the picture on the left.



Door Type - Georgian 2 Glass Type - TGH Satinized (Min. Glass Width 230mm) Colour - Green



Door Type - Georgian 2 Glass Type - TG8 (Min. Glass Width 155mm) Colour - Anthracite Grey



Door Type - Georgian 2 Glass Type - TG76 (Min. Glass Width 200 mm) Colour Red



Door Type - Georgian Solid Glass Type - TGS01 Patinated (Min. Glass Width 170 mm) Colour Agate Grey

- White
- Cream
- Red
- Blue
- Bog Oak
- Green
- Light Oak
- Rosewood
- Charwell Green
- Anthracite Grey
- Silver Grey
- Burgundy
- Agate Grey



Door Type - **Kildare** Glass Type - **TG160 Satinized**
(Min. Glass Width 200 mm) Colour **Green**



Door Type - **Kildare** Glass Type - **TG100**
(Min. Glass Width 250 mm) Colour **Bog Oak**



Door Type - **Kildare** Glass Type - **TG501 Patinated**
(Min. Glass Width 170 mm) Colour **Agate Grey**



Door Type - **Kildare** Glass Type - **TG215** (Min. Glass Width 140mm) Colour **Silver Grey**

Doors fitted with a Heritage Slam Lock, it is recommended to have a PVC threshold or Storm Guard Plus rebated threshold only.
Please Note : Not a Storm Guard or a Storm Guard Plus Threshold.

The Palladio Door Collection

Specifications

Palladio Doors	65mm fibreglass reinforced Mono-coque Composite Door. Patented Design protected in Europe by patent no 1786176, Canadian and US Pending	
Palladio Colours	White, Cream, Red, Blue, Green, Bog Oak, Rosewood, Anthracite Grey, Charwell Green, Light Oak, Silver Grey, Agate Grey and Burgundy. <i>Please note: Half Sidelight Panels are not available in Silver Grey, Agate Grey or Burgundy.</i>	
Avant Garde Colours	White, Cream, Red, Blue, Bog Oak, Chartwell Green, Anthracite grey, Silver grey, Burgundy, Agate grey	
Double Rebate	Double rebate using two seals achieving excellent draught proofing	
Single Door Slab Size	<p>Palladio Collection</p> <p>Leaf Min. 782 mm x 1955mm Single Door Min. 878 mm x 1951 mm Only Max 910mm x 2095 mm With Frame Max. 1006 mm x 2191mm Please note: Minimum Size 858 with 57mm frame on lock side. With low Stormguard Plus threshold, max height 2181mm, min 1942mm With low Stormguard Plus rebated, max height 2162mm, min 1922mm With low Stormguard threshold, max height 2163mm, min 1923mm With 57mm uPVC threshold, max height 2171mm, min 1931mm</p>	<p>Avant garde Collection</p> <p>Leaf Min. 782 mm x 1855mm Single Door Min. 878 mm x 1951 mm Only Max 970mm x 2135 mm With Frame Max. 1066 mm x 2231mm Please note: Minimum Size 858 with 57mm frame on lock side. With low Stormguard Plus threshold, max height 2221mm, min 1942mm With low Stormguard Plus rebated, max height 2202mm, min 1922mm With low Stormguard threshold, max height 2203mm, min 1923mm With 57mm uPVC threshold, max height 2211mm, min 1931mm</p>
Heritage Slam Lock with Leaf Only	Less 96mm from complete door with frame Available for Linair and Kommetling Profile only. Min. Leaf Height 1900mm including 7200 pull handle, 600 curved handle and Slendertech handle	
Heritage Slam Lock with Frame	Min Size 878 - <i>Avant Garde</i> - Barcelona, Milan, Madrid, Matisse, Gauguin Min Size 911 - Paris, London, Rome, Viking, Edinburgh, Seville, T&G, Picasso, Rubens, Turner, Orpen, Monet, Joyce, Oxford, Belfast, Albany, Cashel, Glasgow, Kensington Min Size 901 - Dublin, Giza, Santiago, Cambridge, Kildare	
Heritage Slam Lock And Frame With Escutcheon	Min Size 878 - <i>Avant Garde</i> - Barcelona, Milan, Madrid, Matisse, Gauguin Min size 916 - Georgian, Naples, Cairo, Palermo Min size 891 - Sunbeam, T&G, Paris, London, Rome, Viking, Edinburgh, Seville, Picasso, Rubens, Turner, Orpen, Monet, Joyce, Oxford, Belfast, Albany, Cashel, Glasgow, Kensington Min size 901 - San Marco, Dublin, Giza, Santiago, Cambridge, Kildare	
Warning	Doors fitted with a Heritage Slam lock, it is recommended to have a PVC Threshold or Storm Guard Plus Rebated Threshold only. Please Note : Not A Storm Guard or a Storm Guard Plus Threshold	
U Value rating	Door body U Value - 0.205, Triple glaze U value - 1.1, combined U value - 0.64 Solid Door U Value including frame - 0.85 / Glazed Door U Value including frame - 0.98	
Palladio Triple Glazing	Triple glazed units using warm edge, available in all doors. Backing glass, available as standard in Clear, Cotswold, Minister, Stippolyte and Flemish. * other obscure glass available optional extra (time delay). All satinized triple glazed units available with clear glass only.	
Avant Garde Triple Glazing.	Backing glass, available as standard in Clear, Stippolyte, Minister, Flemish and Satin. Please note Glass units are not replaceable TGS602, TGS604, TGS605, TGS607, TGS608 Not available with Midrails or Toplights, available Full length only	
Lock type	2 hook 2 shootbolt 4 roller and deadlatch / Heritage Slam lock optional extra / PAS 23/24 Approved Thumb turns to be used with the Heritage Slam lock All door locks have a 12 month guarantee	
Door numerals Avant Garde numerals	Supply only available 0-9 in Gold, Chrome, Black, Brushed Steel and Smokey Chrome. Brushed steel only.	
Warning	In the event of a door being fitted behind a Glazed Patio Door, the area needs to be well ventilated to prevent the excessive build up of heat. Due to the manufacturing process Satinized designs and Flemish glass may have imperfections as the raw material is prone to slight blemishes.	
Hardware	High quality handle, letter plate, urn door knocker solid or with spylview, all available with 5 year warranty. MANUFACTURED TO BS 7412. Please Note: Letterboxes can be fitted at the bottom of all doors if requested, this however is not compliant with building regulations.	
Avant Garde Hardware Hardware Colour	Black, Gold, Bright Chrome, Brushed Steel, Smokey Chrome and White. <i>(Please note letterbox and door knocker not available)</i> Door knobs and docters knocker supplied only in Gold and Chrome. <i>(Please note gold and chrome handle and letterbox may vary slightly in colour from the doctor knocker.)</i>	
Handle Maintenance	Stainless pull handles must be maintained every few months with soap and water to avoid discolouration. Do not use any abrasive cleaners	
Hinge type	Rebated hinge available White, Caramel, Black and Cream	
PVC outerframe Sculptured	70mm with galvanized steel reinforcing	
Threshold	Extra strong - standard and low thresholds available	

Please note, owing to the photographic and printing process used, colour may vary from the printed brochure. Images shown are for illustrative purposes only. Actual product appearance and placement of furniture may vary.



Door Type - Giza

Door Type - Naples

Obscure Glass



Stippolyte



Minister

Side Panels

