



- NOTES**
- All dimensions in millimetres unless otherwise shown.
  - All levels in metres above Ordnance Datum (mAOD) unless otherwise shown.
  - All dimensions to be checked on site and any discrepancies reported to Landscape Architect or Employer before pricing / work starts.
  - Any ambiguities or discrepancies within this drawing and any other information given elsewhere must be reported to the Landscape Architect or the Employer for clarification prior to pricing or construction works commencing.
  - All drawings to be read in conjunction with other drawings and specification information as appropriate.
  - Refer to relevant Engineer's and Architect's information as appropriate for confirmation of all engineering and architectural details (including base and sub-base formation layers).
  - All works to be carried out in accordance with the latest British Standards and appropriate codes of practice as a minimum.
  - Unless noted as Construction Status, all information shown is NOT for construction. Clarification to be sought from the Landscape Architect or the Employer prior to construction works commencing.

- KEY**
- Scope Of Works Boundary (As shown on Employers Requirement Drawing)
  - Dashed line indicates furniture re-location works outside of ERs boundary
  - Existing trees to be retained
  - No works to be within RPAs (RPA indicatively shown in blue dashed line)
  - Existing trees to be removed

- PAVING**
- P01 Proposed paving blocks AG Plaza, refer to detail for paving spec and pattern
  - P01.1 Proposed paving blocks AG Plaza, refer to detail for paving spec and pattern
  - P02 Existing paving to be made good where affected by the works
  - P03 Existing bitumen macadam surface to be made good where affected by the works
  - PB1 Parking bays, white lining as shown
  - YL Yellow lining to re-routed existing pedestrian walkway
  - Tac1 Natural stone corduroy tactile paving
  - Tac2 PCC corduroy tactile paving
- Refer to drawings -DT-L-0201 to -DT-L-0203 for tactile paving details
- VG Ventilation grating for existing facade brick vents
- For proposed levels, refer to drawing PL-L-0031 General Arrangement - Paving Plan

- KERBS AND EDGES**
- K1 PCC kerb 125x255mm with 125mm upstand. AG TerraKerb Pearl
  - K2 PCC kerb 125x255mm laid flush. AG TerraKerb Pearl to match K1 (matching drop kerb as necessary)
  - K3 PCC pin kerb 100x200mm laid flush. AG TerraKerb Pearl to match K1

- DRAINAGE**
- CD Channel drain, to Civil Engineer's detail. Cast Iron heelsafe grating, black finish.
  - SD Galvanised facade slot drain, to Civil Engineer's detail. To be installed tight up against the building threshold
  - IC Recessed inspection cover, infilled with paving. Cover must be aligned with paving coursing. Galvanised finish
  - WpH Weep hole in brickwork at paving level. To be maximum of 1/2 brick void. Refer to Civil Engineer's design for confirmation of drainage proposals.

- BOUNDARY TREATMENTS**
- W1 Concrete retaining wall 500mm wide. Gradient to top to match adjacent paving, refer to detail
  - (R1) Vertical bar railing fixed to W1 retaining wall. To achieve 1100mm overall guarding height, refer to detail
  - W2 Concrete retaining wall 200mm wide.
  - W3 Existing wall to be retained
  - W4 Brick wall 215mm wide with brick on edge coping
  - (R2) Railing fixed to concrete foundation at base of brick wall. To achieve 1100mm overall guarding height

- STEPS**
- STP1 Existing steps to be retained, cleaned and made good where affected by the works. New step flags to each step tread. Natural stone tactile flags to top and bottom. 55mm x 55mm Bronze finish step nosing to be inset to steps.
  - STP2 Proposed steps with step flag tread and riser. Natural stone tactile flags to top and bottom. 55mm x 55mm Bronze finish step nosing to be inset to step flags.
  - STP3 Proposed steps with step flag tread and riser (with contrasting colour nosing). PCC tactile flags to top and bottom.
- Refer to drawings -DT-L-0201 to -DT-L-0203 for step and handrail details

- FURNITURE**
- BCH1 Existing benches. To be cleaned, made good and re-sited
  - BIN1 Existing bin. To be cleaned, made good and re-sited
  - CS1 Existing timber decking cycle store. To be cleaned, made good and re-sited
  - CS2 Existing sheffield type cycle stands. To be cleaned, re-painted and re-sited
  - SN1 Existing Colosseum totem sign to be retained
  - CPY Temporary canopy to disabled parking bays (client provision, not part of contracted works)
  - BT1 Bistro tables and chairs Refer to Drg. No. 53CA07-SRLA-TH-GF-DT-L-0901 for details

- PLANTING**
- Refer to planting plan
- PL1 Perennial planting, ground floor beds
  - PL2 Perennial planting, wall beds (with drip irrigation, refer to drawing -0063 General Arrangement - Irrigation)
  - PL3 Hedge and block planting
  - PL4 Climbing Plants (1no. to be planted/replaced as per Employers Requirements provision plus additional 1no. failed plant)

Rev	Date	Description	Drn	Chk
P05	21/09/2023	Outdoor furniture now included in contracted works - note updated. Parking to south re-configured to align with chamber. Note to indicative RPA added.	SWR	SWR
P04	18/07/2023	Channel drain to base of access path removed - to Civil Engineer's design	SWR	SWR
P03	14/07/2023	Updated to respond to client team comments, reflects ERs design with some Derogation as discussed. Refer to Stage 4 report for Derogation schedule.	SWR	SWR

SR Landscape Architecture  
www.sr-la.co.uk  
studio@sr-la.co.uk

Watford Town Hall  
Morgan Sindall

General Arrangement - Public Realm

(S1) Issued for co-ordination

Drawing Number: 53CA07-SRLA-TH-GF-PL-L-0001

Revision: P05

Scale: 1:100 @ A1

Date: 07/06/2023

Drawn by: SWR

Checked by: SWR

