

External Roof Profile

# Vieo Roof

Data Sheet

EC 25-454 Vieo

# External Roof Profile – Vieo Roof

## Application

Vieo Roof is an external standing seam interlocking roof profile specifiable independently or as the external finish of a Vieo Roof system. The Vieo Roof profile is available in steel or aluminium, and can be rolled off-site or on-site depending on project requirements.

## Standard Specification

- EC 25-454 Vieo roof profile available in 0.7mm steel or 0.9mm aluminium
- All coating options achieve BROOF(T4) to BS EN 13501-5:2016. Contact the Technical Team for more information
- Profile lengths can be supplied to site up to 14 metres using conventional transport methods
- Profile lengths can be supplied to site up to 22 metres using special transport methods at additional cost
- Profile lengths above 14 metres can also be rolled on-site to meet specific project requirements

## Coatings

The Vieo Roof profile is available in a number of coating options. When specified in steel, both Colorcoat Prisma® and Colorcoat HPS200 Ultra® are available as external coating options, with the choice dependent upon the end use and environment of the building. When specified in aluminium, Arconic PVDF and Polyester Polyamide (ARS) are available as external coating options. Contact our [Technical Team](#) for further information regarding the above.

## Product Parameters

Parameters	
On-site Rolling Availability	Yes
Natural Self Curve Min Radii Concave*	15m
Natural Self Curve Min Radii Convex*	15m
Smooth Curve Availability	Yes
Smooth Curve Minimum Sheet Length	2.0m
Smooth Curve Maximum Sheet Length	20m
Crimped Curve Availability	No
Weight (0.7mm)	6.34 kg/m <sup>2</sup>
Weight (0.9mm)	2.87 kg/m <sup>2</sup>

# Build a Better Future Together

Euroclad Group Limited

Wentloog Corporate Park  
Wentloog Road, Cardiff CF3 2ER  
United Kingdom

Phone: +44 (0) 2922 010101

Email: [rcs.technical@eurocladgroup.com](mailto:rcs.technical@eurocladgroup.com)

[www.eurocladgroup.com](http://www.eurocladgroup.com)



Please scan  
the QR code or  
[click here](#) for  
the most up to  
date version of  
this document.



Care has been taken to ensure that the contents of this publication are accurate, but Euroclad Group Ltd and its subsidiary companies do not accept responsibility for errors or for information that is found to be misleading. Suggestions for, or description of, the end use or application of products or methods of working are for information only and Euroclad Group Ltd and its subsidiaries accept no liability in respect thereof.

Colorcoat®, Colorcoat Prisma®, Confidex® and Galvalloy® are registered trademarks of Tata Steel UK Limited.