

Schedule of Works _ Connecting Unit 6 and 7, The Old Fox Yard, Stowmarket, IP14 1AB

Existing Fabric:

The dividing wall between the two units is masonry at ground level and timber frame at first floor level. The masonry wall has a newer cement plaster and painted finish.

Schedule of works:

- remove a small amount of building fabric in the areas identified on the plans and in the DAS photos.
- Use temporary supports where necessary
- Install concrete lintels to ground floor openings and timber lintel to first floor opening.
- Finish over lintels and reveals of new openings to match finish of adjacent walls (i.e plaster to match adjacent).

Mitigations:

Only fabric identified on the drawings will be removed; surrounding building fabric will remain undisturbed.

Temporary propping will be used to maintain building structure while new lintels are being installed.