INSPECTIONS REQUIRED BY THE HIGHWAYS INSPECTOR

The contractor shall give advance notice to suffolk county council to allow the inspector proper inspection and checking of the works at the following designated stages:

1) Prior to start of works a photographic record of existing highway condition adjacent to development to be agreed and recorded


2] Start of the works 3) Before back filling any trenches under new highway


- 4] Completion of formation 5) Completion of sub-base
- 6) Arrival and planting of trees
- 7) Laying of base 8] Laying of binder course

9] Laying of surface course

before the inspector will be recommend works for interim/adoption No street light shall be installed until its final position has been agreed with the street lighting engineer

10] All damage to existing highway resulting from construction traffic to be repaired Retained pedestrian access Existing vehicula access +20-38 +20/2 +20/2 +20/2 +20/2 +28.2 +28.2 +28.2 +28.2 Redes





The hazards noted are in addition to the normal hazards and risks faced by a competent contractor when dealing with the type of works detailed on this drawing.

CONSTRUCTION RISKS:

- 1. Confined spaces entry and hazardous waste materials / gas.
- 2. Deep manholes / excavations 3. Contractor to locate services prior to excavating.
- 4. Asbestos may be present.
- 5. Drainage connection requires deep excavation temp works required.
- 6. Existing drains to be protected and bridged over where required.
- . Works adjacent to busy road and river. Watercourse / ditch levels may rise rapidly following prolonged periods of rainfall.
- 8. Soft ground during construction works particularly in wet weather.

MAINTENANCE/CLEANING RISKS:

- . Pavement deformations to be monitored to ensure that designed pavement falls are maintained. If significant deformation is allowed to propagate then localised flooding could occur. 2. Silt traps, drainage channels, permeable pavements and
- inspection chambers require the standard periodic inspection regime and cleaning routine to ensure continued performance and
- reduce the risk of flooding. 3. Works adjacent to Watercourse / ditch. Watercourse / ditch levels will vary during heavy rainfall events.4. Potential for soft spots within existing ground after heavy rainfall.
- 5. Dust and noise impacts on local community.
- Existing live services and utilities.
 Deep manholes / excavations appropriate entry equipment
- required. 8. Soft ground during construction works particularly in wet weather.

DEMOLITION / ADAPTION RISKS:

- Apparatus located in landscaped areas has not been designed to support heavy vehicle loading. . The surface water drainage apparatus has been designed to
- accommodate the designed catchment area. no additional areas of hardstanding can be connection into the system without risk of localised flooding on site.
- 3. Hazardous waste materials / dust and debris releasd into the air. 4. Deep manholes / excavations - appropriate entry equipment required. . Works adjacent to river. Watercourse / ditch levels will vary during
- heavy rainfall events.
- 6. Unknown ground conditions during / after heavy rainfall.
 7. Soft ground during construction works particularly in wet weather.

PRELIMINARY DRAWING:

This drawing is for preliminary purposes only and must not be read as a construction issue. The design is not fixed and design changes are likely.

| | 1 | | | I |
|-----|----------|-------------|----|-------|
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| P1 | 28.07.23 | Preliminary | JS | JRS |
| Rev | Date | Description | By | Check |
| | | | | |

Copyright: The copyright of this drawing is vested in Schema Engineering To be read in conjunction with all other project related drawings, reports

- and surveys etc. It shall not be used without permission by anyone for any purpose. Do not scale this drawing electronically or manually.
- Work to figured dimensions only. All dimensions are in metres unless stated otherwise.
- Do not turn on layers that have been turned off. Do not thaw layers that have been frozen.

Client

Cocksedge Building Contractors Project Barret's Lane, Needham Market Suffolk IP68DL Title Section 38 Plan General Arrangement Status Preliminary Scale @ A1 1:300 Sustainable design+ planning Job Number By Checked By Date 0304 JRS July 2023 JS Revision P1

| Drawing | No |
|---------|----|
| C45 | 0 |



| | CARRIAGEWAY CONSTRUCTION |
|--------|--|
| | FOOTPATH CONSTRUCTION |
| | ADOPTABLE RAMP FOR RAISED TABLE |
| \sum | SHARED SURFACE RAMP |
| | PRIVATE SW DRAINAGE TO HIGHWAYS STANDARE |
| | ROAD GULLY |
| HB — | PRECAST CONCRETE HALF BATTERED KERB WITH 125mm UPSTAND |
| BN — | PRECAST CONCRETE FULL FACE KERB WITH 25mm UPSTAND |
| 1 | PRECAST CONCRETE DROPPER KERB |
| ED — | PRECAST CONCRETE FOOTWAY EDGING |
| 03— | PRECAST FLUSH CHANNEL SQUARE FOR PRAM CROSSING |
| o5 —— | PRECAST FLUSH CHANNEL SQUARE FOR ADOPTABLE VEHICLE CROSSOVER |
| 00 | EXISTING GROUND LEVEL |
| | PRAM CROSSING WITH BLISTER PAVING |
| | EXTENT OF S38 WORKS |
| | |
| | S104 DRAINAGE EASEMENT |
| F | PROPOSED STREETLIGHTS - REFER TO SCC STREETLIGHT DESIGN DRAWING NUMBER: |
| | NOTE: ALL PRIVATE DRIVEWAYS ACCESSING ADOPTABLE HIGHWAY WILL HAVE A MINIMUM |

X=2M BY Y=2M PEDESTRIAN VISIBILITY SPLAYS

- $\Theta - - -$
- НВ НВ Н - BN - BN - BN DK

HICH

SIRTH

- ED ED ED — КD3 — КD3 -

through site

- Reinstated entra taszHuinstlea Hou