Air Conditioning

Product Information

MSZ-SF25VE2 Inverter Heat Pump Classic Wall Mounted System Making a World of Difference



These models offer industry leading noise levels as low as 21dBA and have a distinctively styled front panel that not only looks appealing, but also helps to make cleaning of the unit easier. To aid control and energy saving, the new universal controller has in built 7 day timeclock.

Key Features

- Swing Vane Mode with Auto Vane Shutter
- Wide Swing and Long Airflow Mode available on GF models only
- Infra-red remote controller
- Econo Cool allows set temperature to be raised by 2°C without any loss of comfort and a 20% gain in energy efficiency
- Auto-Restart
- Quiet operation
- Auto-Changeover
- Hot Start draught prevention
- Optional Anti-Allergy Enzyme filter artificial enzymecatalyst on the filament catches allergens
- Nano Platinum filter (only with GF models) incorporates nanometre sized platinum-ceramic particles that generate stable antibacterial and deodourising effects
- Quick clean design
- Replace Technology available
- I-Save Recalls the preferred (preset) temperature via a single button
- The MSZ-SF25VA is compatible with City Multi when used in conjuction with PAC-LV11M LEV kit



Air Conditioning | Heating Ventilation | Controls



Product Information

MSZ-SF25VE2 Inverter Heat Pump Classic Wall Mounted System

Making a World of Difference

Air Conditioning

MSZ-SF - INDOOR UNIT		MSZ-SF25VE2
CAPACITY (kW)	Heating (nominal)	3.2 (1.0-4.1)
	Cooling (nominal)	2.5 (0.9-3.4)
	Heating (UK)	2.66 (0.83-3.41)
	Cooling (UK)	2.5 (0.89-3.37)
SHF (nominal & UK)		0.92
COP / EER (nominal)		4.10 / 4.17
SCOP / SEER (BS EN14825)		4.4 / 7.6
ErP ENERGY EFFICIENCY CLASS Heating/Cooling		A+ / A++
AIRFLOW (I/s) Heating - Silent-Lo-Mid-Hi-Shi		58-68-112-137-172
Cooling - Silent-Lo-Mid-Hi-Shi		58-68-92-120-152
PIPE SIZE mm (in)	Gas	9.52 (3/8")
	Liquid	6.35 (1/4")
SOUND PRESSURE LEVEL (dBA) Heating/Cooling - Silent-Lo-Mi-Hi-Shi		19-24-34-39-45 / 19-24-30-36-42
SOUND POWER LEVEL (dBA)		57
DIMENSIONS (mm)	Width x Depth x Height	798 x 195 x 299
WEIGHT (kg)		10
ELECTRICAL SUPPLY		Fed by Outdoor Unit
FUSE RATING (BS88) – HRC (A)		6
INTERCONNECTING CABLE No. CORES		4

DIMENSIONS	
Air in Installation plate	798
8	61 577 160

MUZ-SF - OUTDOOR UNIT	MUZ-SF25VE
SOUND PRESSURE LEVEL (dBA) Heating/Cooling	48 / 47
SOUND POWER LEVEL (dBA) Cooling	58
WEIGHT (kg)	31
DIMENSIONS (mm) Width x Depth x Height	800 x 285 x 550
ELECTRICAL SUPPLY	220-240v, 50Hz
PHASE	Single
SYSTEM POWER INPUT (kW) Heating/Cooling (nominal)	0.780 / 0.600
Heating/Cooling (UK)	0.71 / 0.49
STARTING CURRENT (A)	3.9
SYSTEM RUNNING CURRENT (A) Heating/Cooling [MAX]	3.9 / 3.2 [8.4]
FUSE RATING (BS88) - HRC (A)	10
MAINS CABLE No. CORES	3
MAX PIPE LENGTH (m)	20
MAX HEIGHT DIFFERENCE (m)	12
CHARGE R410A (kg)	0.7 (7m)





Telephone: 01707 282880

email: air.conditioning@meuk.mee.com web: www.airconditioning.mitsubishielectric.co.uk

UNITED KINGDOM Mitsubishi Electric Europe Living Environmental Systems Division Travellers Lane, Hatfield, Hertfordshire, AL10 8XB, England General Enquiries Telephone: 01707 282880 Fax: 01707 278881 IRELAND Mitsubishi Electric Europe Westgate Business Park, Ballymount, Dublin 24, Ireland

Country of origin: United Kingdom – Japan – Thalland – Malaysia. (Mitsubish) Electric Europe 2015. Mitsubish) and Mitsubishi Electric are trademarks of Mitsubishi Electric Europe B.V. The company reserves the right to nake any variation in technical specification to the equipment described, or to withdraw or replace products without prior notification or public amountement. Mitsubishi Electric is constantly developing and improving its products. All descriptions, illustrations, drawings and specifications in this publication present only general particulars and shall not form part of any contract. All goods are supplied subject to the Company's General Conditions of Sale, a copy of which is available on request. Third-party product and brand remes may be trademarks or registered trademarks of their respective owners.









Telephone: Dublin (01) 419 8800 Fax: Dublin (01) 419 8890 International code: (003531)





Mitsubishi Electric UK's commitment to the environment





