



Appendix 1 Tree survey and explanatory notes

Site: Land south of Thorpe Road Weeley
 Date of Survey: 12/03/2017 29/10/2017

OHLE = over head line equipment

Surveyor: J Choat
 Weather: Hot/dry/clear

Estimated due to dense ivy/surrounding vegetation or 3rd party ownership.

Tree ref	Species	Height in m	Stem diameter in mm	RPA in M2	Radial distance required for RPA	Branch spread				Height of crown clearance in m	Age class	Ground condition	Water demand	Observations	Preliminary management recommendations	Works urgency	Estimated remaining contribution in years	Category grading
						N	E	S	W									
G2	Oak, Hazel, Sweet Chestnut, Hawthorn	12	500	113.112	6	3	3	3	3	2	M	Bare soil	Varies	Small woodland/copse with PROW running through, possibly historical holloway. Evidence of coppicing, although secondary woodland flora, hazel indicating at least 200 years of age. Good wildlife interest.	None	0	30+	A1/2/3
G3	Oak, Hazel, Sweet Chestnut, Hawthorn, Field maple	12	500	113.112	6	3	3	3	3	2	M	Bare soil	Varies	Small woodland/copse with PROW running through, possibly historical holloway. Evidence of coppicing, although secondary woodland flora, hazel indicating at least 200 years of age. Good wildlife interest.	None	0	30+	A1/2/3
T1	Ash	16	600	162.88128	7.2	5	5	5	5	3	M	Bare soil	Moderate	Base not inspected due to dense surrounding vegetation. Growing within small woodland / copse.	None	0	30+	A1/2/3
T2	Oak	16	760	261.3339648	9.12	7	7	7	7	3	M	Bare soil	High	Growing within woodland/copse. Good condition.	None	0	30+	A1/2/3
T3	Oak	16	590	157.4971488	7.08	5	5	5	5	3	M	Bare soil	High	Twin stem tree. Growing within woodland/copse. Good condition.	None	0	30+	A1/2/3
G4	Oak, Hazel, Sweet Chestnut, Hawthorn	12	500	113.112	6	3	3	3	3	2	M	Bare soil	Varies	Small woodland/copse with PROW running through, possibly historical holloway. Secondary woodland flora. Good wildlife interest.	None	0	30+	A1/2/3
G5	Oak, Hazel, Sweet Chestnut, Hawthorn	12	500	113.112	6	3	3	3	3	2	M	Bare soil	Varies	Small woodland/copse with PROW running through, possibly historical holloway. Secondary woodland flora. Good wildlife interest.	None	0	30+	A1/2/3
T4	Oak	16	940	399.7830528	11.28	7	7	7	7	3	M	Bare soil	High	Aged tree. Ivy clad to 12m.	None	0	30+	A1/2/3
G6	Oak, Hawthorn	5	200	18.09792	2.4	2	2	2	2	3	M	Bare soil	High	Group forming hedgerow with some gaps. Oak have been reduced/pollarded below OHLE. Good screening from Railway. Good wildlife interest and connecting to other green features.	None	0	30+	A1/2/3
T5	Oak	10	500	113.112	6	5	5	5	5	2	EM	Bare soil	High	Base not inspected due to dense surrounding vegetation. Branch snapped out at 5m.	Remove torn branch and clean wound.	3	30+	A1/2/3
T6	Willow	4	300	40.72032	3.6	0.5	1	1	1	2	EM	3rd party	High	3rd party tree. Recent pollard.	None	0	10+	C1
T7	Lime	7	300	40.72032	3.6	3	3	3	3	2	EM	3rd party	Moderate	3rd party tree. Some pruning on property side.	None	0	20+	C1
H1	Thorn, poplar	3	300	40.72032	3.6	3	3	3	3	0	M	Bare soil	High	Good screening trees. Succession of blackthorn on outer edge. 1 poplar has failed in to field.	Remove failed poplar, check base of remaining tree once area cleared.	3	20+	B1/2/3
G7	Oak, Hawthorn	5	300	40.72032	3.6	2	2	2	2	3	M	Bare soil	High	Group forming hedgerow with some gaps. Good screening from Railway. Good wildlife interest and connecting to other green features.	None	0	30+	A1/2/3
H2	Thorn	1.5	75	2.54502	0.9	0.5	0.5	0.5	0.5	0	Y	Bare soil	High	Planted hedgerow maintained at current dimensions cut on regular pruning regime. Good connections to other wildlife / green features.	None	0	20+	B1/2/3
H3	Thorn, bramble, ivy	1.5	200	18.09792	2.4	0.5	0.5	0.5	0.5	0	M	Bare soil	High	Thorn clad with bramble and ivy. Good Wildlife interest and connection to other wildlife /green features.	None	0	20+	B1/2/3
G8	Holly	5	460	95.7379968	5.52	3	3	3	3	1	EM	Bare soil	Low	Group of coppice hedgerow trees forming large coppice stool.	None	0	30+	A1/2/3
T8	Oak	5	460	95.7379968	5.52	3	3	3	3	1	EM	Bare soil	High	Low branches. Good condition.	None	0	20+	B1/2/3
T9	Hawthorn	4	380	65.3334912	4.56	2	3	2	1	0	M	Bare soil	High	Asymmetric crown. Leaning stem.	None	0	20+	C1/2/3
T10	Oak	5	400	72.39168	4.8	3	3	3	3	2	EM	Bare soil	High	Ivy and bramble clad, unable to fully assess base.	Clear ivy and bramble and reassess.	3	20+	B1/2/3
T11	Oak	11	980	434.5310592	11.76	6	6	6	6	2	M	Bare soil	High	Aged tree. Good condition. Low branches.	None	0	30+	A1/2/3
T12	Oak	12	600	162.88128	7.2	6	6	6	6	4	M	Bare soil	High	Good condition.	None	0	30+	A1/2/3
T13	Hawthorn	5	520	122.3419392	6.24	1	1	1	3	2	M	Bare soil	High	Decaying/lapsed coppice. Good wildlife value due to age and decaying parts.	None	0	15+	C1/2/3
T14	Oak	14	800	289.56672	9.6	6	6	6	6	2	M	Bare soil	High	3rd party tree. Slightly suppressed crown. Unable to fully inspect base. Aged tree.	None	0	30+	A1/2/3
T15	Oak	14	880	350.3757312	10.56	6	6	6	6	2	M	Bare soil	High	3rd party tree. Lapsed pollard, some veteran associations. Good wildlife tree.	None	0	30+	A1/2/3
H4	Thorn, bramble, ivy	1.5	200	18.09792	2.4	0.5	0.5	0.5	0.5	0	M	Bare soil	High	Thorn clad with bramble and ivy. Good Wildlife interest and connection to other wildlife /green features.	None	0	20+	B1/2/3
H5	Thorn, bramble, ivy	1.5	200	18.09792	2.4	0.5	0.5	0.5	0.5	0	M	Bare soil	High	Thorn clad with bramble and ivy. Good Wildlife interest and connection to other wildlife /green features.	None	0	20+	B1/2/3
H6	Thorn, bramble, ivy	1.5	200	18.09792	2.4	0.5	0.5	0.5	0.5	0	M	Bare soil	High	Thorn clad with bramble and ivy. Good Wildlife interest and connection to other wildlife /green features.	None	0	20+	B1/2/3
H7	Thorn, bramble, ivy	1.5	200	18.09792	2.4	0.5	0.5	0.5	0.5	0	M	Bare soil	High	Thorn clad with bramble and ivy. Good Wildlife interest and connection to other wildlife /green features.	None	0	20+	B1/2/3
H8	Thorn, bramble, ivy	1.5	200	18.09792	2.4	0.5	0.5	0.5	0.5	0	M	Bare soil	High	Thorn clad with bramble and ivy. Good Wildlife interest and connection to other wildlife /green features.	None	0	20+	B1/2/3
T16	Yew	9	870	342.4578912	10.44	4	4	4	4	1.5	M	Bare soil	Low	Tree of significant age, fairly unusual for the area, set within historical property providing good historical context.	None	0	50+	A1/2/3

T17	Horse chestnut	3	310	43.4802528	3.72	3	3	3	3	1	EM	Bare soil	Moderate	Spiral cracks, old bleeding canker symptoms.	Consider felling	3	10	C1
T18	Holly	10	450	91.62072	5.4	3	3	3	3	2	M	Bare soil	Low	Good condition.	None	0	30+	A1/2/3
T19	Holly	5	230	23.9344992	2.76	2	2	2	2	1	EM	Bare soil	Low	Multi stem tree.	None	0	20+	B1/2/3
G9	Fruit	3	200	18.09792	2.4	2	2	2	2	1	EM	Grass	Moderate	Group of fruit trees with leaning stems and basal wounds.	None	0	10+	C1
T20	Yew	6	320	46.3306752	3.84	2	2	2	2	1	EM	Bare soil	Low	Sparse crown. Climber within crown.	Remove climber.	3	20+	C1
H9	Leyland cypress	3	200	18.09792	2.4	1	1	1	1	0	EM	Bare soil	High	Poor condition. Browning/die-back.	None	0	10	C1
H10	Thorn, holly, ivy	4	300	40.72032	3.6	1	1	1	1	0	EM	Bare soil	Varies	Hedgerow with some gaps, some non native trees beyond. Reasonable screening. Bases not inspected.	None	0	20+	B1/2/3
T21	Holly	4	180	14.6593152	2.16	1	1	1	1	2	Y	Bare soil	Low	Sparse crown. Die back of higher apex.	Monitor, likely to decline further.	3	10	C1
T22	Ash	17	500	113.112	6	1	4	4	4	3	M	Bare soil	Moderate	Ivy clad, situated within hedgerow. Unable to fully assess.	Sever ivy to 1m and re-inspect.	3	20+	A1/2/3
T23	Ash	19	700	221.69952	8.4	6	6	6	6	3	M	Bare soil	Moderate	Ivy clad, situated within hedgerow. Unable to fully assess. Occasional deadwood within crown.	Remove any deadwood over public right of way. Sever ivy to 1m and re-inspect.	3	20+	A1/2/3
T24	Hawthorn	5	400	72.39168	4.8	2	2	2	2	2	M	Bare soil	High	Aged tree. Multi stem tree. Some minor crown decline. Situated within copse/small woodland.	None	0	20+	A1/2/3
T25	Sweet chestnut	15	400	72.39168	4.8	3	3	3	3	3	M	Bare soil	Moderate	Situated within small copse/woodland. Base restricted due to woodland debris.	None	0	20+	A1/2/3
G10	Thorn, sweet chestnut, ash	17	400	72.39168	4.8	4	4	4	4	0	M	Bare soil	Varies	Small copse/woodland, good screening, wildlife and landscape value.	None	0	30+	A1/2/3
T26	Oak	12	630	179.5766112	7.56	4	4	4	4	3	M	Bare soil	High	Former hedgerow tree, hedgerow since grubbed out.	None	0	30+	A1/2/3
T27	Oak	12	700	221.69952	8.4	4	4	4	4	3	M	Bare soil	High	Former hedgerow tree, hedgerow since grubbed out. Aged tree with some veteran associations.	None	0	30+	A1/2/3
T28	Oak	12	1005	456.9837912	12.06	4	4	4	4	3	M	Bare soil	High	Former hedgerow tree, hedgerow since grubbed out. Aged tree with some veteran associations.	None	0	30+	A1/2/3
G11	Ash, alder, hawthorn, willow	15	700	221.69952	8.4	4	4	4	4	0	M	Bare soil	Varies	Wetland trees rooted along Holland Brook, tree synonymous with type of habitat. Occasional alder have been previously coppiced.	Habitat could be improved with addition of further native stock and perhaps 1 - 2 native black poplar (preferably female). Some works to	3	30+	A1/2/3
H11	Oak, field maple, hawthorn, blackthorn	8	400	72.39168	4.8	4	4	4	4	0	M	Bare soil	Varies	Hedgerow of native specimens rooted on railway boundary. Good screening properties. Good wildlife properties with good connectivity to aged trees and other green features.	None	0	30+	A1/2/3



Explanatory Notes

Referencing

Each tree is given a unique reference number and plotted on the attached plans for clear identity. Individual trees are referenced as T1, T2 etc, Groups G1, G2 etc Hedgerows H1, H2 etc and Woodlands W1, W2 etc

Species

All species are recorded using common names. Identification is made using experience and knowledge.

Tree dimensions

Tree height is measured and recorded in meters and taken from the base of the stem to the tip of the crown. Height is estimated using experience and knowledge.

Diameter at Breast Height (DBH) is measured at approximately 1.5m from the ground up the stem and is measured and recorded in millimetres. DBH is measured accurately using a diameter tape.

Crown spread is measured in meters from the stem to the extent of the crown spread to each compass point (NESW). Crown spread is estimated using experience and knowledge.

Crown clearance is the height from ground level to the lowest branch and is measured in meters. Crown clearance is estimated using experience and knowledge.

Age class

Age class falls in to 4 categories:

Y	Young
EM	Early Mature
M	Mature
OM	Over Mature

Observations

The biological condition of the tree is assessed and noted. Notable defects are recorded; fruiting bodies, cankers, die back, exudates, etc are recorded.

The mechanics of the tree are assessed and noted. Notable defects are recorded; buckling, rib formation, stresses, bulges, soil cracks, large cavities or wounds, tight branch junctions, etc are recorded.

Preliminary management recommendations

Tree management is recommended following the assessment of physiological and structural condition. Recommended works may include, no work required, crown reduction, crown lift, fell, crown thin, monitor etc.

Estimated remaining contribution in years

An estimate of remaining life expectancy recorded in years. Estimated remaining contribution is made using experience considering the structural and physiological condition of the tree, nuisance, previous management, etc.

Category grading and colour coding on plan

A (Green square) high quality and value

B (Blue square) moderate quality and value

C (Grey square) low quality and value

U (Red Square) those that cannot be retained as living trees



Sub categories

- 1 arboricultural values
- 2 landscape values
- 3 cultural values, including conservation

Works priority

- 1 Works required immediately to make the tree safe
- 2 Works required within 60 days
- 3 Works required as part of routine operations
- 0 no works required

Appendix 2 Barrier construction profile

Permission to reproduce extracts from BS 5837:2012 is granted by the British Standards Institution (BSI). No other use of this material is permitted. The complete British Standard can be purchased from the BSI online shop: <http://shop.bsigroup.com/en/ProductDetail/?pid=000000000030213642>

Diagram 1 Weldmesh panels with block supports pegged to brace light impact




Diagram 2 Weldmesh panels with block supports and further block supports to brace intermediate impacts





Diagram 3 Weldmesh panels with scaffold frame posts driven into the ground to brace heavy impacts



Construction Exclusion Zone

These trees have been retained and protected as part of the planning permission for this site.

Any breach of the protection will result in enforcement action from the Local Authority.



Appendix 4 Tree protection plan



Key Infrastructure Works Timing

All methods reference below are accessible to the plan are to be read in conjunction with the arboricultural method statement (MSP) 05/000001.

The installation and removal of the tree protection is to be supported by the project arboricultural and environmental records. Further details are provided in the arboricultural plan and method statement.

Phase 1 - Tree works, see schedule below, no other measures with this work.

Phase 2 - Risk / Assessment phase barrier protection

- Tree work to be performed in accordance with method statement provided below.
- Small trees with a diameter less than 100mm should be protected by tree guards.
- Cable or weatherproof alternatives to barrier.


Phase 3 - Intensive soil aeration. Aerial excavation in per method statement provided below at location shown in drawings below.

Phase 4 - Soft soil and landscaping phase barrier protection

- Where trees to be removed prior to the start and end of the tree removal work, showing access to the approved soft soil and landscaping, see method statement below.

Phase 5 - Removal of ground and barrier protection.

- Where trees to be removed prior to the start and end of the tree removal work, showing access to the approved soft soil and landscaping, see method statement below.



Construction Exclusion Zone

No access is permitted

The trees beyond this protected zone are subject to planning conditions and statutory protection

Any breach of this zone will result in enforcement action by the Local Authority

Sequential method statement for hand excavation and root pruning - H1, T4, G1, G2, H4, H5, H6, G10, T1, T2 and T4


1. Remove ground surface with soil removal up to 100mm, above all parts outside of the RPA, to be replaced with a layer of 100mm of good quality topsoil, spread and level to the original ground level. This should be done before the start of the excavation.
2. Where roots are encountered but shall be pushed to side of pit or diameter.
3. If any exposed roots should immediately be wrapped or covered in plastic to prevent desiccation and to protect them from rapid temperature changes.
4. If required, where any roots with a diameter less than 25mm (use a sharp tool to provide a clean cut) across the cross section near to a root protection zone.
5. Root pruning should be done to the extent of the root system, if this is necessary, then require an arboriculturalist to check the site to avoid likely impact upon tree health and future growth.
6. Prior to backfilling any roots should be removed from the protection wrapping and surrounded by chert sand or other loose granular fill, before soil is returned to replace. The backfill is to be firm and compacted to the original level.
7. Monitor tree health during root growth season. Check leaf colour, size, density and extension growth. Monitor again the following season.

Soft surface within RPA


- No tractor or other heavy plant (including excavators) is to be used within working on surface. It is to be used for the purpose of removing soil and ground compaction.
- Cultivation is to be completed using manual hand tools.
- Existing soil is to be used, where additional soil is required it should be contained in a well defined and suitable P11, texture and structure for the site and planting existing trees/shrubs.
- Damage to roots is to be avoided, large structural roots may be seen at or near the surface and where they reduce from the stem of the tree from large buttresses, other exposed structural roots need to be supported by a suitable method of support.
- Once the excavation work is complete, the remaining soil should be levelled out using a suitable method of compaction that provides continued soil conditions of air drainage and water penetration.
- Planting is to be done with care and to avoid covering tree roots, generally, planting should be completed outside the RPA.

Legend:


Tree reference




Tree and crown spread




Root protection area




Temporary barrier protection




Trees / hedges to be removed



Hand excavation




Crown reduction



Notes:

This drawing was produced in colour, a monochrome copy should not be relied upon.



Project: Land south of Thorpe Road, Weeley

Drawing Title: Tree Protection Plan

TPS
Arboricultural Consultancy

25 Frietuna Road
Frinton On Sea
Essex
CO130QP

T +44 (0)7813204621
E info@treeplanningolutions.co.uk
W www.treeplanningolutions.co.uk

Date: 1st March 2023

Scale: 1:1000 @ A0

Drawing Number: TPSarb6990117 TPP Rev B



Appendix 5

Example of site monitoring form

Tree Planning Solutions

Contract Monitoring Form

Details

Date	
Time	
Surveyor	
Client	
Site	
Ref	

Trees

Tree ref	Condition	Recommendations

Barrier

Tree ref	Barrier type	RPA radial distance as per planning permission	Actual barrier radial distance at site	Condition of barrier	Condition of signage	Comments

Tree Planning Solutions

Ground Protection

Tree ref	Type of ground protection installed	RPA distance as per planning permission	Actual distance of ground protection at site	Condition of ground protection	Comments

Additional Comments