0 | 3m | 6m | 9m | 12m | 15m | 18m | 21m | 24m | 27m | 30m

SOVA SURVEYS

Station	Easting	Northing	Level
A	10000.000	6000.000	50.000

Notes :
Stations * and * are marked with a P, Hilti Nail/ Wooden Stake.

ON DETAIL SURVEY

AB	Air Brick	ER	Earth Rod	SA	Survey Abandoned
AC	Asbestos Cement	FFL	Finished Floor Level	S/A	Soakaway
ACU	Air Conditioning Unit	FH	Fire Hydrant	SC	Stop Cock
AD	Assumed Direction	FO	Fibre Optic Cover	SI	Spun Iron
AL	Air Line	FS	Flag Staff	SL	Soffit Level
AR	Assumed Route	G	Gully	SP	Sign Post
ASP	Artificial Stone Paving	GV	Gas Valve	Spr	Spring
AT	Air Tower	IC	Inspection Cover	S/R	Steel Railings
AV	Air Valve	IL	Invert Level	SS	Structure Support
BB	Belisha Beacon	JB	Junction Box	ST	Stop Tap
BD	Back Drop	KO	Kerb Outlet	Stn	Survey Station
BdL	Bed Level	LB	Letter Box	SV	Sluice Valve
BH	Borehole	LP	Lighting Column	SVP	Soil Vent Pipe
Bk	Brick	LH	Lamp Hole	Tac	Tactile Paving
BL	Basement Light	MB	Mooring Bollard	TBM	Temporary Bench Mark
BOL	Bollard	MH	Manhole Cover	TC	Telecom Cover
BR	Brick	Mkr	Marker Post	TCB	Telephone Call Box
BS	Bus Stop	MP	Mile Post/Stone	TOV	Top Of Vegetation
BT	British Telecom Cover	NFI	No Further Information	TH	Trial Hole / Pit
BTB	British Telecom Box	NM	Node Marker	THL	Threshold Level
CAB	Cabinet	NP	Name Plate	Tk	Tank
Cam	Camera	NPV	No Pipes Visible	T/F	Top Of Fence
CAT	Catenary Level	OH	Overhead	T/W	Top Of Wall
CC	Control Cabinet	OSA	Off Survey Area	TP	Telegraph Pole
CH	Chainage	PO	Post	TS	Traffic Signals
ChL	Channel Level	PB	Post Box	UTGA	Unable to Gain Access
CI	Cast Iron	PBM	Permanent Bench Mark	UTL	Unable to Lift
CL	Cover Level	PE	Polyethylene	UTS	Unable to Survey
Co	Concrete	PGM	Permanent Ground Marker	VC	Vitrified Clay
CP	Catch Pit	PLA	Plastic	VDP	Vehicle Detector Pads
CPS	Conc Paving Slabs	PM	Parking Meter	VP	Vent Pipe
CTV	Cable TV	PU	Pump	VR	Vapour Recovery
CUL	Culvert	PVC	Polyvinylchloride	VTP	Vertical Pipe
D	Depth (deep)	PZ	Piezometer	WL	Water Level
DI	Ductile Iron	RE	Rodding Eye	WM	Water Meter
dil	Dilapidated	Ri	Riser	WO	Water Wash Out
dis	Disused	RFL	Roof Level	WS	Window Sample
D/S	Downstream	RP	Reflector Post	WV	Water Valve
EB	Electricity Box	RS	Road Sign		
EC	Electricity Cover	RWP	Rain Water Pipe		
EP	Electricity Pole	S	Stump		

ON FENCES/WALLS/DIVISIONS

B/W	Barbed Wire Fence	P/W	Post and Wire Fence
CrB	Crash Barrier	S/F	Safety Fence
C/B	Close Boarded Fence	S/R	Steel Railings
C/I	Corrugated Iron Fence	W/M	Wire Mesh Fence
C/L	Chain Link Fence	BW	Brick Wall
E/F	Electric Fence	CW	Concrete Wall
FPB	Panel / Board Fence	DSW	Dry Stone Wall
H/R	Hand Rail	R/W	Retaining Wall
I/R	Iron Rail Fence	SW	Stone Wall
P/L	Palisade Fence	T/H	Temp. Heras
P/R	Post and Rail Fence		

ON BUILDINGS

ASB	Asbestos	RL	Ridge Level
AV	Air Vent	RWC	Rain Channel
CL	Cill Level	RWP	Rain Water Pipe
CH	Ceiling Height	SA	Spring Of Arch
CHM	Chimney Stack Height	SCH	Suspended Ceiling Height
DH	Door Head	SD	Sliding Door
DP	Down Pipe	SOIL	Soil Pipe
EL	Eave Level	SVP	Sewer Vent Pipe
F	Frame Height	THL	Threshold Level
FD	Folding Door	USB	Underside Of Beam
GRL	Glazed Roof Light	WH	Water Heater
HL	Head Level	WP	Waste Pipe
PART	Partitioning	WST	Water Storage Tank
PL	Parapet Level		

SITE

Rev:	Comments	By	Chkd	Date
-	-	-	-	--

Project Name
18 Chester Street Oxford OX4 1SN

File Name:
SOVA230932 TOPO

Drawing Title :
Topo Survey Of
Sheet (1 of 1 A1)

Client: Izzy MacPhail	Date: 25/10/2023
	Scale: A1 @ 1:100

Drawn by:	Checked by:	Project Code:	Revision:
SOVA - MM	SOVA - SCM	SOVA230932	---

Grid Orientation:	Site Level Datum
Arbitrary	Arbitrary

All dimensions are to be checked on site where applicable.This drawing must not be scaled, and only written dimensions should be respected.

Tree species and sizes on this drawing are not guaranteed, and if critical should be verified by an arboriculturist. Tree spreads are average about the bole, and heights are approximate at the time of the survey.