

# Cottage Mixture



**Ibstock**  
At the heart of building



## Product Information

Ibstock Code:	4001
Type:	Stock
Facing Description:	Sandfaced
Dry Brick Weight (kg):	2.3kg
Pack Quantity:	500
Packaging (standard):	Banded (plastic)
Factory:	Ashdown

## Technical Specification (to BS EN 771-1)

Brick Dimensions (L x W x H mm):	215x102x65
Size Tolerances Mean & Range:	T1 R1
Configuration:	Single Frog
Voids (%):	6-11
Compressive Strength (N/mm <sup>2</sup> ):	30
Active Soluble Salts:	S2
Water Absorption (% weight):	15
Durability:	F2
Gross Dry Density (Sound Insulation) (Kg/m <sup>3</sup> ):	1550
Equivalent Thermal Conductivity "K" value 5% Exposed:	Refer to Ibstock
Initial Rate of Absorption (Suction Rate) (Kg/m <sup>2</sup> /min):	Refer to Ibstock
EAN:	5036335023976