

[Home](#) > [Products](#) > TAURUS


TAURUS

Exterior Wall Light with Dark Sky Optic

- Available in 3 outputs
- Dark sky optic to reduce upward light output with less than 2% ULOR
- High performance optic for maximum spacing and distribution
- Photocell option available
- Gear options including DALI and emergency available
- Maximum of 15m spacing, at 3m mounting height
- Die-cast aluminium body finished in grey (RAL 9006) or black (RAL 9005)
- Integral driver
- Supplied in neutral white (4000K) LED
- Up to 138 lumens per Watt efficacy



Product Filter

If you don't have a part number, use the filter to find what you need. Select product and light source first to narrow the output and power options.

Colour Temperature (CCTK)

Vision Controls

Emergency

DALI

[Product Leaflet](#)
[Instruction leaflet](#)
[Polar Curve](#)
[Photometric Data](#)

Order Code	Description	lm	W	lm/W	H(mm)	L(mm)	W(mm)	D(mm)
TAU80NWB	6W - 4000K - Black	800	6	133	220	295	0	165
TAU80NWG	6W - 4000K - Grey	800	6	133	220	295	0	165
TAU180NWB	13W - 4000K - Black	1800	13	138	220	295	0	165
TAU180NWG	13W - 4000K - Grey	1800	13	138	220	295	0	165
TAU300NWB	24W - 4000K - Black	3000	24	125	220	295	0	165
TAU300NWG	24W - 4000K - Grey	3000	24	125	220	295	0	165

2 MILLION
LED CHIPS
PLACED A MONTH

5 LIGHTING
EXPERIENCE
CENTRES

UK
FACTORIES

OVER
50 YEARS
LIGHTING
EXPERIENCE

Contact us

+44 (0)1527 517 777

+44 (0)1952 292 441 (Technical)

Tamlite, Field Sales Centre
Park Farm Industrial Estate,
Redditch, Worcestershire, B98 0HU

[About us](#) »

[T-Word](#) »

[Environmental](#) »

[Careers](#) »

[TRUST TAMLITE](#) »

Opening times

Monday - Friday
08:30 - 17:00



Lighting for a Living