

[Home](#) > [Products](#) > [EXPLORER Range](#) > EXPLORER



EXPLORER

High Performance Asymmetric Floodlight

- High performance floodlight suitable for car parking and sports applications
- Available in 6 different outputs and 3 body sizes
- Available in asymmetric or double asymmetric beam angles
- Fully adjustable stirrup
- Glass cover
- CRI: Ra>80
- Die-cast aluminium body finished in grey (RAL 9006)
- Integral driver
- Supplied in neutral white (4000K) LED
- Up to 125 lumens per Watt efficacy

IP65

IK08

7 YRS

$\leq 28K$
lm

≤ 240
W

≤ 125
lm/W

Product Filter

If you don't have a part number, use the filter to find what you need. Select product and light source first to narrow the output and power options.

Colour Temperature (CCTK)

Vision Controls

DALI

[Instruction leaflet](#)

[Polar Curve](#)

[Photometric Data](#)

[Product Leaflet](#)

| Order Code | Description | lm | W | lm/W | L(mm) | W(mm) | D(mm) |
|------------|-----------------------------|-------|-----|------|-------|-------|-------|
| EPR480ANW | 40W - Fixed Output - 4000K | 4800 | 40 | 120 | 359 | 308 | 82 |
| EPR720ANW | 60W - Fixed Output - 4000K | 7200 | 60 | 120 | 420 | 370 | 83 |
| EPR1250ANW | 100W - Fixed Output - 4000K | 12500 | 100 | 125 | 420 | 370 | 83 |
| EPR1800ANW | 150W - Fixed Output - 4000K | 18000 | 150 | 120 | 420 | 370 | 83 |
| EPR2400ANW | 200W - Fixed Output - 4000K | 24000 | 200 | 120 | 452 | 462 | 87 |
| EPR2800ANW | 240W - Fixed Output - 4000K | 28000 | 240 | 117 | 452 | 462 | 87 |

2 MILLION
LED CHIPS
PLACED A MONTH

5 LIGHTING
EXPERIENCE
CENTRES

UK FACTORIES

OVER
50 YEARS
LIGHTING
EXPERIENCE

Contact us

+44 (0)1527 517 777

+44 (0)1952 292 441 (Technical)

Tamlite, Field Sales Centre
Park Farm Industrial Estate,
Redditch, Worcestershire, B98 0HU

[About us](#) »

[T-Word](#) »

[Environmental](#) »

[Careers](#) »

[TRUST TAMLITE](#) »

Opening times

Monday - Friday
08:30 - 17:00



Lighting for a Living