

TC LIGHTING COLUMNS

Aluminium lighting columns



Features:

Hot dipped galvanised to BSEN 150 1461:2009

Tapered conical design

Traditional tubular style with semi-flush door

Smooth anodised finish

Wide range of brackets and spigots available

Note: Wind speed and environmental conditions vary greatly across the British Isles. It is therefore vital to consult with Tamlite Technical to obtain correct advice on column selection (Light, medium or heavy duty steel)

Construction:

Mild galvanised steel or aluminium alloy tubing

Designed to BS5649 series 1300

Root section externally bitumen coated

Options:

No options available

TC LIGHTING COLUMNS

Aluminium lighting columns

Order Codes

All dimensions are in millimetres

Order code	Description	Lumens (lm)	Total power (W)	Efficacy (lm/W)	Weight (kg)
TC8MLD	8000mm Medium duty				85.00
TC6M	6000mm Light duty steel				51.00
TC5M	5000mm Light duty steel				40.00
TC4M	4000mm Light duty steel				33.00
TC3M	3000mm Heavy duty steel				28.00
TC8MHD	8000mm Heavy duty steel				100.00
TC6MHD	6000mm Heavy duty steel				68.00

Dimensions

All dimensions are in millimetres

Order code	A	B	C
TC8MLD	8000	89	8
TC6M	6000	76	6
TC5M	5000	76	5
TC4M	4000	76	4
TC3M	3000	76	3
TC8MHD	8000	114	8
TC6MHD	6000	89	6

Installation instructions:

Root mounted to planting depth shown via flange plate and bolt-template. See installation sheet.

To specify:

Steel or aluminium lighting column as per Tamlite TC

range

Please Note: Order codes listed are for standard (non-emergency) versions only. For all other gear options, please contact Tamlite Lighting.