

PRODUCT DATA SHEET

EVERBUILD® Lumberjack® Woodworm Killer

Ready to use woodworm treatment

PRODUCT DESCRIPTION

EVERBUILD® Lumberjack® Woodworm Killer is a ready to use treatment for the eradication of all types and life stages of wood boring insects and their larvae, specifically woodworm. The added insecticide also aids to actively kill the woodworm and protect against re-infestation. Micro fine actives penetrate deep into the wood.

USES

- Can be used on most internal furniture, woodwork and joinery such as doors, window frames, roof timbers, floorboards, joists, rafters, etc. It can be over painted, stained, varnished, or polished when dry if required
- For interior use only

CHARACTERISTICS / ADVANTAGES

- Kills all types of wood boring insects
- Penetrates deep into the wood for long lasting protection
- Overpaintable
- Ready to use, no need to dilute
- Fast drying

PRODUCT INFORMATION

| | |
|---------------------|---|
| Packaging | 5ltr tin |
| Appearance / Colour | Clear |
| Shelf Life | Use within 2 years of manufacture. |
| Storage Conditions | Store between 5 and 25°C in original containers away from children. |
| Density | ca. 1 g/cm ³ |

APPLICATION INFORMATION

| | |
|-------------|---|
| Consumption | <ul style="list-style-type: none"> ▪ Apply 2 coats at a rate of 1 litre of product per 3 - 4m² of surface. ▪ Dip end grains for a minimum of 3 minutes or flood thoroughly where dipping is not possible. ▪ Drying time is approximately 1 hour depending on temperature. |
|-------------|---|

APPLICATION INSTRUCTIONS

SUBSTRATE QUALITY / PRE-TREATMENT

Ensure that timber to be treated is clean. Any paint or other surface coatings should be removed prior to application. Remove any badly infected or structurally unsound timber and replace with sound timber prior to application.

APPLICATION

Read statutory conditions relating to use prior to application. Shake well before use. Apply by brush, spray or dipping. Apply a minimum of two coats if brushing or spraying. The second coat should be applied after the first coat has soaked in but before it is dry. Pay particular attention to thoroughly soaking the end grain. Where possible, dip or flood the end grains of the timber for maximum protection. NOTE: product is milky out of the can drying clear.

CLEANING OF TOOLS

Remove as much product as possible from brush or spray then clean with soapy water.

LIMITATIONS

- Ready to use - do not dilute.
- Do not use in food preparation areas.
- Do not use externally.
- It is the user's responsibility to determine suitability for use. If in doubt, contact Technical Services Department for advice.

VALUE BASE

All technical data stated in this Data Sheet are based on laboratory tests. Actual measured data may vary due to circumstances beyond our control.

LOCAL RESTRICTIONS

Note that as a result of specific local regulations the declared data and recommended uses for this product may vary from country to country. Consult the local Product Data Sheet for exact product data and uses.

ECOLOGY, HEALTH AND SAFETY

See MSDS for full list of hazards.

LEGAL NOTES

The information, and, in particular, the recommendations relating to the application and end-use of Sika products, are given in good faith based on Sika's current knowledge and experience of the products when properly stored, handled and applied under normal conditions in accordance with Sika's recommendations. In practice, the differences in materials, substrates and actual site conditions are such that no warranty in respect of merchantability or of fitness for a particular purpose, nor any liability arising out of any legal relationship whatsoever, can be inferred either from this information, or from any written recommendations, or from any other advice offered. The user of the product must test the product's suitability for the intended application and purpose. Sika reserves the right to change the properties of its products. The proprietary rights of third parties must be observed. All orders are accepted subject to our current terms of sale and delivery. Users must always refer to the most recent issue of the local Product Data Sheet for the product concerned, copies of which will be supplied on request.

EVERBUILD BUILDING PRODUCTS LTD

Site 41, Knowsthorpe Way
Cross Green Industrial Estate
Leeds, LS9 0SW
Tel: 0113 240 3456
Web: www.everbuild.co.uk
Twitter: @everbuild

SIKA LIMITED

Watchmead
Welwyn Garden City
Hertfordshire, AL7 1BQ
Tel: 01707 394444
Web: www.sika.co.uk
Twitter: @SikaLimited