

| Installation Type | Unit of Measure | Capacity/Flow rate (1) | Use Factor (2) | Fixed use (litres/person/day) (3) | Litres/person/day = [(1)x(2)] + (3) (4) |
|--|--|---|----------------|-----------------------------------|---|
| WC (single flush) | Flush Volume (litres) | | 4.42 | 0.00 | 0 |
| WC (dual flush) | Full flush Volume (litres) | 4.3 | 1.46 | 0.00 | 6.28 |
| | Part flush Volume (litres) | 2.6 | 2.96 | 0.00 | 7.70 |
| WC (multiple fittings) | Average effective flushing Volume (litres) | | 4.42 | 0.00 | 0 |
| Taps (excluding kitchen/utility room taps) | Flow rate (litres/min) | 4.00 | 1.58 | 1.58 | 7.90 |
| Bath (where shower also present) | Capacity to overflow(litres) | 215.00 | 0.11 | 0.00 | 23.65 |
| Shower (where bath also present) | Flow Rate(litres / minute) | 7.00 | 4.37 | 0.00 | 30.59 |
| Bath Only | Capacity to overflow(litres) | | 0.50 | 0.00 | 0 |
| Shower Only | Flow Rate (litres/minute) | | 5.60 | 0.00 | 0 |
| Kitchen/Utility room sink taps | Flow rate (litres/minute) | 7.00 | 0.44 | 10.36 | 13.44 |
| Washing Machine | (Litres/kg dry load) | 8.17 | 2.1 | 0.00 | 17.157 |
| Dishwasher | (Litres/place setting) | 0.80 | 3.6 | 0.00 | 2.88 |
| Waste disposal unit | (Litres/use) | <input type="checkbox"/> Present | 3.08 | 0.00 | 0 |
| Water Softener | (Litres/person/day) | | 1.00 | 0.00 | 0 |
| | (5) | Total Calculated use (litres/person/day) =SUM(column 4) | | | 109.60 |
| | (6) | Contribution from greywater (litres/person/day) | | | 0 |
| | (7) | Contribution from rainwater (litres/person/day) | | | 0 |
| | (8) | Normalisation factor | | | 0.91 |
| | (9) | Total internal water consumption = [(5)-(6)-(7)]x(8) (litres/person/day) | | | 99.73 |
| | (10) | External water use | | | 5.0 |
| | (11) | Total water consumption (Building Regulation 17.K) =(9)+(10)(litres/person/day) | | | 104.7 |

| Installation Type | Make/Model (mandatory) | Litres/Person/Day |
|---------------------------|--|-------------------|
| WC (dual flush) | Duravit 2169090000 | 13.98 |
| Taps | restricted to 4 ltrs Hansgrohe Vivenis 110 & 3 | 7.90 |
| Baths (shower(s) present) | Senna | 23.65 |
| Showers (bath(s) present) | restricted to 7 ltrs Hansgrohe HG Ecostat S | 30.59 |
| Kitchen Taps | restricted to 7 ltrs Rangemaster Twin Lever | 13.44 |
| Washing Machines | default | 17.157 |
| Dishwasher | Bosch Series 2 SMV2ITX18G | 2.88 |

