



LEGEND

- To be removed
- New / To be replaced
- New Wall

2 Carefully strip paint from existing beams

Existing stair balustrade/railing to be replaced with new balustrade/railing. Existing structural post to be removed. Please see structural engineers drawing for detail.

5 Existing shelving to be replaced with new shelves

6 All existing doors to be removed and replaced with new doors.

7 Existing wardrobe doors to be replaced with new doors within the master bedroom and dressing room.

9 New built-in joinery

FLOORS

- 10 Bathroom floors : Tumbled limestone tile
- Chaunceys Engineered Oak
- 220mm wide, 20mm thick