

Proposed Site Section

Comparison to existing building on site

Notes:

All work is to be carried out to the latest current British Standards Codes of Practice and recognised working practices.

All work and materials should comply with Health and Safety legislation.

All dimensions are in millimetres unless where explicitly shown otherwise. The contractor should check and certify all dimensions as work proceeds and notify the agent of any discrepancies.

Do not scale off the drawings, if in doubt ask.

HAD & Co. are not liable for any work undertaken prior to Full Planning Consent and or Building Regulations Approval.

Any structural works should be checked and verified by a suitably qualified structural engineer before works commence.

All drainage is assumed and should be clarified on site by the contractor.

COM REGULATIONS 2015
The citent must abide by the Construction Design and Management
Regulations 2015. The elient must appoint a contractor, if more than one
contractor is to be involved, the client will need to appoint (in writing) a
principal designer (to plan, manage and coordinate the planning and
design work) and a principal contractor (to plan, manage and coordinate
the construction and ensure there are arrangements in place for managing
and organising the project).

Domestic clients
The domestic client is to appoint a principal designer and a principal
contractor when there is more than one contractor, if not your duties will
automatically transferred to the contractor or principal contractor.
The designer can take on the duties, provided there is a written agreeme
between you and the designer to do so.

The Health and Safety Executive is to be notified as soon as possible before construction work starts if the works:

(a) Last longer than 30 working days and has more than 20 workers working simultaneously at any point in the project.

Or: (b) Exceeds 500 person days.

(b) Exceeds 500 person days.

PARTY WALL ACT
The owner, should they need to do so under the requirements of the Party Wall Act 1996, has a duty to serve a Party Structure Notice on any adjoining owner if building work on, to or near an existing Party Wall involves any of the following:

Support of bear through wall

Raising a wall or cutting off projections

Demolition and rebuilding

Underpinning

Insertion of lead flashings

Excavations within 3 metres of an existing structure where the new foundations will go deeper than adjoining foundations, or within 6 metres of an existing structure where the new foundations are within a 45 degree line of the adjoining foundations. A Party Wall Agreement is to be in place prior to start of works on site.

THERMAL BRIDGING
Care shall be taken to limit the occurrence of thermal bridging in the insulation layers caused by gaps within the thermal element, (i.e. around windows and door openings). Reasonable provision shall also be made to ensure the extension is constructed to minimise unwanted air leakage through the new building fallor.

MATERIALS AND WORKMANSHIP

All works are to be carried out in a workmanlike manner. All materials and workmanship must comply with Regulation 7 of the Bullding Regulations, all relevant Birthis Standards, European Standards, Agreement
Certificates, Product Certification of Schemes (Kite Marks) etc. Products conforming to a European technical standard or harmonised European product should have a CE marking.

Revisions List:



Address: Hapton Hall Farm Lyndale Road Hapton Burnley BB11 5RD

	Title: Site Section					Drawn: NME			
	Client: Brett Morgan					Checked: CC			
	Date: 03-11-2023 Drawing No: HAD3854-04					Paper: A3			
						Scale: 1:100			
	Revision:								