Revised Planting

T1 Sweet Gum
T2 Silver Birch
T3 False Acacia
T4 Whitebeam
T5 Portugese Laurel
T6 Apple
T7 Purple Leaf Cherry, Prunus Serrulata, Royal Bergundy.

G1 Western Red Cedar
G2 Lime

Extra Planting with native specimen to encourage biodiversity:

H1 Retain existing hedging and shrubs and reinforce with additional planting as required using mixed hedging 70-90cm.
Ratio: 35% Hawthorne,
35% Blackthorne,
10% Wild Cherry,
10% Honeysuckle.

Sunny Beds
A selection of shrubs eg. Lavender, Campanilla, Scabus, Sedum and Penstemon (Flame).

Shady Beds
Eg. Hostas, Spring bulbs, Digitalis, Euphorbia (Amygdaloides/Robbiae/ Cyparissias).

6x Bird Boxes - Woodcrete Boxes, 2 no. to each plot, to be fixed to the trunks of the existing trees.

PORTOFINO LONDON

SITE
7 Beaconfields, Sevenoaks, Kent, TN13 2BH

PROJECT
The demolition of existing dwelling and garage and the erection of 3 detached houses with garages and parking

REVISED LANDSCAPE PLAN

NOTES:
- Red dotted line represents the outline of the consented bungalow

SCALE	DATE	DRAWN BY
1:250@A3	March 2021	Darcie/Tim

AMENDMENTS
A, Consented Bungalow

DRAWING NO.	REVISION
7B/DS2/14	B

SEAWARD CAD SERVICES
D. F. SEAWARD
17 Argyll Street
Ryde
PO33 3BZ
07815157920