

Glazing Specification for replacement / new wooden Herbert Collins windows

Double Glazing will be manufactured and installed to the following specification –

External glass - 6.4mm laminated with soft coat (for sound reduction)

Cavity - 6mm white warm edged spacer bar and argon gas

Internal glass - 4mm with low iron (for thermal performance)

Total thickness - 16.4mm

All openers to have individual panes of glass to match existing front and side windows of 62 Bassett Green Road.

W/c and bathroom windows to have frosted glass for privacy.

All panes of glass to be secured into openers using glazing tape, Accoya glazing beads and clear sealant as required.