

SEWAGE  
PERMIT

CANAL

Mr michael wood  
Humbleton Hall Fitling Road,  
Humbleton,  
Hull,  
North Humberside,  
HU11 4NS,  
England

Our ref: SEWQ Issue

Your ref:

Reg. Customer I.D. No

Date: 29/11/2010

Dear Mr wood

**Environmental Permitting (England and Wales) Regulations 2010  
Registering an exempt Water Discharge Activity**

**Exemption Ref:** EPR/HH0166KQ/A001

**Location:** Humbleton Hall Fitling Road, Humbleton, Hull, North Humberside, HU11 4NS, England

Thank you for sending us the details for your proposed registration.

I am pleased to confirm that we have registered your activity as exempt from requiring an Environmental Permit. Details of your registration are included in the attached schedule.

Please remember that your exemption is only valid if you adhere to our conditions. Failure to do so is an offence. A full list of conditions is available on our website.

<http://www.environment-agency.gov.uk/business/topics/water/110593.aspx>

If the activity you have registered is also controlled by an existing permit (or discharge consent) you need to tell us if you wish to surrender the permit. You should use form E1 available on our website

<http://www.environment-agency.gov.uk/business/topics/permitting/117672.aspx>

Alternatively, a paper copy of the form is available on request. You can contact us on 08708 506 506\*, we are available Monday to Friday, from 8am to 6pm.

Yours sincerely

Calls to 0870 numbers: Weekday Daytime calls to 0870 numbers cost 8p, plus up to 6p per minute from BT Weekend Unlimited. Mobile and other providers' charges may vary.

The Environment Agency does not endorse any commercial business so you cannot use our logo on your website or promotional literature. However you can state that you are registered as exempt by the Environment Agency, if this is the case, and have a link to our website.

Environment Agency, National Customer Contact Centre, 99 Parkway Avenue, Parkway Business Park, Sheffield, S9 4WF  
Customer Services Line: 08708 506 506  
Fax: 01142 626 697  
Email: [enquiries@environment-agency.gov.uk](mailto:enquiries@environment-agency.gov.uk)

2141\_EPS\_PermitIssue\_E

Jo Price  
Customer Operations Manager

Calls to 0870 numbers: Weekday Daytime calls to 0870 numbers cost 8p, plus up to 6p per minute from BT Weekend Unlimited. Mobile and other providers' charges may vary.

The Environment Agency does not endorse any commercial business so you cannot use our logo on your website or promotional literature. However you can state that you are registered as exempt by the Environment Agency, if this is the case, and have a link to our website.

Environment Agency, National Customer Contact Centre, 99 Parkway Avenue, Parkway Business Park, Sheffield, S9 4WF  
Customer Services Line: 08708 506 506  
Fax: 01142 626 697  
Email: [enquiries@environment-agency.gov.uk](mailto:enquiries@environment-agency.gov.uk)

2141\_EPS\_PermitIssue\_E

## Schedule of exempt operations

Name:	Mr michael wood
Trading name (if any):	
Address:	Humbleton Hall Fitling Road, Humbleton, Hull, North Humberside, England, HU11 4NS
Exemption Ref No:	HH0166KQ
Address where the operation can be carried out:	Humbleton Hall Fitling Road, Humbleton, Hull, North Humberside, England, HU11 4NS
National Grid Reference:	TA2330635044

### Activity Number & Description:

## 2 Operations

### 2.1 Permitted activities

2.1.1 001 - Discharge of sewage effluent to surface water of five cubic metres per day or less. First made on or after 6 April 2010.

### 2.2 The site

2.2.1 The occupier should have obtained any relevant planning and building control approval before seeking registration of an exempt discharge activity.

2.2.2 The maximum daily volume of the discharge shall be 5 cubic metres or less per day as calculated by the method specified in the sewage treatment plant manufacturer's and installer industry Code of Practice 'Flows and Loads 3'.

2.2.3 The sewage shall be solely domestic in origin and contain no trade effluent.

2.2.4 Prior to the discharge, the sewage must have received treatment from a sewage treatment plant designed and constructed according to the relevant British Standard design requirements in force at the time of installation, (currently BSEN 12566:2005 (part 3)) and sized in accordance with industry Code of Practice: 'Flows and Loads 3'.

2.2.5 The discharge must not be within 30 metres of a public foul sewer.

2.2.6 The sewage treatment plant must be installed in accordance with the manufacturer's specification issued at the time of installation or to the guidance given in the appropriate industry operating Code of Practice.

2.2.7 The discharge must be made to a watercourse that has a flow of water throughout the year.

2.2.8 Drainage systems incorporating a partial infiltration system or drainage field prior to discharge to surface waters must include a package sewage treatment plant and the drainage field must be installed within 10 metres of the bank side of the watercourse.

2.2.9 In tidal locations the discharge must be made below the Mean Low Water Springs tide mark.

2.2.10 The location of the discharge must be further than 50 metres of an identified bathing water or a designated shellfishery.

2.2.11 The sewage treatment system shall be operated and maintained in accordance with a maintenance plan

as specified within the manufacturers maintenance instructions or other maintenance schedule adopted by the occupier, or manufacturing industry Code of Practice guides.

2.2.12 Maintenance should be undertaken by those who are competent in respect of the responsibilities to maintain and service the sewage treatment system.

2.2.13 Waste sludge removed from the sewage treatment system must be safely disposed of in an appropriate or controlled manner, using competent disposal contractors.

2.2.14 Records demonstrating compliance with the maintenance and desludging requirements shall be in a legible format and retained for at least 5 years from the date when the records were made.

2.2.15 The discharge must not cause pollution of surface or groundwater.

2.2.16 Details of this registration and associated conditions should be stored in a safe place, and provided to next occupier on change of ownership.

***Date of issue:*** 26/11/2010