

BOW TOP GATES



- Horizontal rails for all gates are 50 x 25 x 2mm
- Hanging and shutting stiles are rectangular hollow section 60 x 40 x 2mm wall thickness
- Gate posts are 80 x 80 x 3.6mm square hollow section minimum
- Automated or manual gate operation available
- Single leaf gates are standard right hand hanging, open inwards
- Self closing gates are left hand hanging, open outwards
- Non self closing gates come complete with hinges, which allow the gate to swing through an angle of 180 degrees, are integral to the construction of the gate and are fully adjustable with tamperproof screws and bolts when the gates are closed, catch fixings and welded steel caps
- Domed post caps
- Option to include finials to special order
- 25 year service life guarantee

Single leaf and double leaf standard heights

- 1.0m
- 1.2m
- 1.5m
- 1.8m other heights to special order



Magnetic latch on a self closing gate

APPLICATIONS

- Parks
- Public Areas
- Schools

COLOURS

- Black RAL 9005
- Green RAL 6005
- Other colours are available on request

FINISHES

- Hot dip galvanised to BS EN ISO 1461 as standard
- Hot dip galvanised and powder coated to BS EN 13438
- Marine coat for installations within 500m of salt water or an estuary