



Photo Impression



Existing

Sign No.	Sign 1 - Dunelm
Type:	1no blackclip box with digi print skin.
Sizes:	5150 x 2500mm Returns: 196mm
Backing:	Target Dibond Backing
Box Finish:	Powder Coated into RAL6018
Illumination	Install LEDs for full face illumination.
Fixing Details:	Primary fixing steel tek screws into internal cladding rails and secondary fixing gash point tek screws.
Sign No.	Sign 2(a) - 2(d)
Type:	4no blackclip flexface boxes
Sizes:	4000 x 2000mm Returns: 196mm
Backing:	Target Dibond Backing sheets
Box Finish:	Boxes are powder coated Black.
Illumination & Skin Face Details:	Boxes are complete with digi printed PVC skins with internal LED illumination
Fixing Details:	Primary fixing steel tek screws into internal cladding rails and secondary fixing gash point tek screws.
Sign No.	Sign 3: Welcome
Type:	1no Flat Dibond Panels with digital printed vinyl to the face
Sizes:	5150 x 895mm
Fixing	Face fixed to glazing mullions using csk screws vinyl dots to cover

This copy has been made by or with the authority of Bidebaldan Council pursuant to Section 47 of the Designs and Patents Act 1988. Unless that Act provides a relevant exception to copyright, the copy must not be copied without the prior permission of the copyright owner.

This Drawing & information contained may not be copied or used without prior consent from Spencer Signs. Colour shown may not accurately match any colour references. Sizes in mm unless stated otherwise.

SPENCER SIGNS Unit 1, 70 Scarborough St., Hull, HU3 4TG Tel: 01482 352000 www.spencersigns.co.uk email: design@spencersigns.co.uk	DRG. NO. 84637	Date 27/03/23	Checked 	Rev.	Date	Initial	Revision Detail
	Drawn By C Wallis	Scale 1:200@A4	Drawing Status PLANNING				

Specification checked and approved for Production By (sign & print name)		Typeface(s)/Colours
C100 M80 Y20 K30	C1 M11 Y100 K0	P305C White
	New 4MM Blue	New 4MM Green
		C M Y K