

Planting Schedules

Single Species Hedgerow Planting Schedule

Plant name	Height (cm)	Root Condition	Habit	Breaks	Density/ lin m	Length (m)	Total No. Plants
<i>Hedgerows (Rows at 300mm centres) Double Staggered Rows</i>							
<i>Carpinus betulus</i>	60-90	B	Branched	3	5	5	25

Herbaceous/ Perennial Planting Schedule

Plant Name	Root condition	Size	Propagation	Planting Mix (m2)	Density (m2)	Total Number Plants
<i>Achillea 'Summer Berries'</i>	C	1L	V	0.5	6	3
<i>Anemantele lessoniana</i>	C	5L	V	1.5	2	3
<i>Bergenia 'Overture'</i>	C	1L	V	0.5	6	3
<i>Carex omithopoda 'Variegata'</i>	C	1L	V	1	6	6
<i>Geranium macrorrhizum</i>	C	1L	V	0.5	6	3
<i>Persicaria affinis 'Superba'</i>	C	1L	S or V	0.5	6	3
		Totals		4.5		21

Planting Specification

Trees and shrubs planted shall comply with BS.3936 (Specification of Nursery Stock) and shall be planted in accordance with BS.4428 (General Landscape Operations) and BS8545:2014 ' Trees from nursery to dependence in the Landscape'. Engineer to refer to soft landscape proposals when undertaking foundation design. Contractor to familiarize themselves with location of underground services using routing plans, CAT scans and onsite survey prior to planting and excavations.

Bare root and root-balled stock to be planted in the dormant season.

All planting stock to be clearly labelled on delivery with the full botanical name. Plant stock to be approved prior to delivery to site and planting and trees be set out by Landscape Architect. All topsoil to be of good quality AS-DUG in accordance with BS 3882.2015. Depths of topsoil (Shrubs- 300mm), Hedgerows (350mm) over free draining subsoil.

Organic soil improvement compost to be dug into all planting areas and used at 1cubic m per 10m2. All planting beds to be mulched in 75mm depth medium grade bark mulch immediately after planting.

If very wet or very dry conditions are found in proposed planting areas the landscape architect shall review planting locations and/or species.

Water planting in first 2 seasons to ensure establishment. Continue to water raised beds beyond this as required.

Any queries in relation to planting schedules, layout or planting stock to be raised with Landscape Architect.

Suitable tree root barriers to be used on boundaries with hard-standing, walling, services, proposed and existing buildings.

FOR PLANNING

525 Helmshore Road, Helmshore.
Rossendale. BB4 4LQ

**Planting Schedules
and Outline Planting
Specification**

SCALE: NTS DATE: July 23

DRAWING: M667/HRH/LAND/02D

