



PLAN VIEW

Key

- A Training aid (White Line)
- B Batting Curtain

Specifications for a Two Lane 'Enclosed' Facility

Playing Surface Dimensions: Two Lanes 33m by 7.3m
 Synthetic playing surface carpets: per lane 33m by 3.65m
 'tp1' premium grade woven artificial carpet construction
 Standard design: two-tone green with blue borders

tp1 Carpet Design Options:
 Single tone green
 Two-tone with dark green borders
 Training Aid: three white stump lines woven into the carpet

Shock Pads: Per Lane
 'tp2' batting area: pace modifying shock pad for the pitching area
 'tp3' bowling area & run-up: load absorbing shock pad

Steelwork System Dimensions: Per Lane
 Height 4m
 Length 18.3m
 Width 3.6-3.65m
 48mm diameter galvanised steel tubes set in a 52mm diameter socket

Design Options:
 Powder coated steelwork: Green or Black
 Lane end gates
 Lane end protection barriers

Netting Systems:
 Protection Tunnels: exclusive to total-play
 One seamless piece of total-play's 'HD' netting secured with
 PVC encapsulated tension wire (Green or Black)
 Batting Curtains (white mesh) 2m by 7.3m

Design Option:
 total-play's 'HD' netting: walled design
 Batting curtains: fitted to surround the batsmen
 Protection Skirt in Green or Black (PVC): protects the bottom
 section of netting, either 0.5m or 1m high

Security Fence:
 All systems can be built with perimeter security fencing and gates.
 Design options include gate width, fence height, colour & type of perimeter safety path

The 'tp365' system designed and installed by total-play Ltd is an England & Wales Cricket Board (ECB) Approved Non-Turf Pitch System