



**LEGEND**


- FD Denotes period door upgraded to fire resisting door as specified
- DB Denote smoke alarm
- DH Denotes heat alarm
- CP Denotes fire alarm control panel
- △ Denotes carbon monoxide detector to BS EN 50291:2002 powered by battery designed to operate for the working life of the alarm
- EEW Denotes emergency egress window with unobstructed opening at least 0.32m<sup>2</sup> and at least 450 high x 450 wide with bottom of opening not more than 1100 above floor



Side elevation



Rev.A gravelled parking area notes added Jan.24



**R.R.RIMMER**  
B.A., Dip. Arch., R.I.B.A.  
CHARTERED ARCHITECT

24 Whitecourt  
Uley  
Dursley  
Gloucestershire GL11 5TG  
Tel: (01453) 861083

**LANCASTER HOUSE, BRISTOL ROAD, THORNBURY BS35 3JA**  
(Grade II Listed Building) - alterations and refurbishment  
**Proposed ground floor plan and side elevation**  
**A2 - Drg. No. 1694/08 Rev.A**

1:100