



JPP Consulting Ltd		Page 1
4, Ironstone Way Brixworth Northampton, NN3 9UD	25910 - Kestrel Way, Luton SW 1 in 1 Year FSR	
Date 13/12/2023 File Network 1.MDX	Designed by TL Checked by TL	
Innovyze	Network 2016.1	

Simulation Criteria for Storm

Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1
Number of Input Hydrographs	0	Number of Storage Structures	10
Number of Online Controls	1	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Profile Type	Summer
Return Period (years)	1	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	20.000	Storm Duration (mins)	30
Ratio R	0.400		

JPP Consulting Ltd		Page 2
4, Ironstone Way Brixworth Northampton, NN3 9UD	25910 - Kestrel Way, Luton SW 1 in 1 Year FSR	
Date 13/12/2023 File Network 1.MDX	Designed by TL Checked by TL	
Innovyze	Network 2016.1	

Online Controls for Storm


Hydro-Brake Optimum® Manhole: SFCC1, DS/PN: S1.009, Volume (m³): 9.4

Unit Reference	MD-SHE-0086-3600-1250-3600
Design Head (m)	1.250
Design Flow (l/s)	3.6
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Application	Surface
Sump Available	Yes
Diameter (mm)	86
Invert Level (m)	121.250
Minimum Outlet Pipe Diameter (mm)	100
Suggested Manhole Diameter (mm)	1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.250	3.6
Flush-Flo™	0.378	3.6
Kick-Flo®	0.770	2.9
Mean Flow over Head Range	-	3.2

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	2.6	1.200	3.5	3.000	5.4	7.000	8.1
0.200	3.4	1.400	3.8	3.500	5.8	7.500	8.3
0.300	3.6	1.600	4.0	4.000	6.2	8.000	8.6
0.400	3.6	1.800	4.3	4.500	6.5	8.500	8.8
0.500	3.5	2.000	4.5	5.000	6.9	9.000	9.1
0.600	3.4	2.200	4.7	5.500	7.2	9.500	9.3
0.800	2.9	2.400	4.9	6.000	7.5		
1.000	3.2	2.600	5.1	6.500	7.8		

JPP Consulting Ltd		Page 3
4, Ironstone Way Brixworth Northampton, NN3 9UD	25910 - Kestrel Way, Luton SW 1 in 1 Year FSR	
Date 13/12/2023 File Network 1.MDX	Designed by TL Checked by TL	
Innovyze	Network 2016.1	

Storage Structures for Storm

Porous Car Park Manhole: S5, DS/PN: S1.004

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	4.8
Membrane Percolation (mm/hr)	1000	Length (m)	27.8
Max Percolation (l/s)	37.1	Slope (1:X)	60.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	123.595	Cap Volume Depth (m)	0.225

Porous Car Park Manhole: S6, DS/PN: S2.000

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	4.8
Membrane Percolation (mm/hr)	1000	Length (m)	20.0
Max Percolation (l/s)	26.7	Slope (1:X)	60.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	123.595	Cap Volume Depth (m)	0.225

Porous Car Park Manhole: S8, DS/PN: S1.005

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	4.8
Membrane Percolation (mm/hr)	1000	Length (m)	22.5
Max Percolation (l/s)	30.0	Slope (1:X)	60.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	123.045	Cap Volume Depth (m)	0.225

Tank or Pond Manhole: SHW2, DS/PN: S1.007

Invert Level (m) 121.800


Depth (m)	Area (m ²)	Depth (m)	Area (m ²)	Depth (m)	Area (m ²)
0.000	35.4	0.800	147.5	0.801	0.0

Porous Car Park Manhole: S11, DS/PN: S3.000

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	4.8
Membrane Percolation (mm/hr)	1000	Length (m)	27.5
Max Percolation (l/s)	36.7	Slope (1:X)	60.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	123.695	Cap Volume Depth (m)	0.225

Porous Car Park Manhole: S12, DS/PN: S3.001

Infiltration Coefficient Base (m/hr)	0.00000	Safety Factor	2.0
Membrane Percolation (mm/hr)	1000	Porosity	0.30
Max Percolation (l/s)	30.0	Invert Level (m)	123.195

JPP Consulting Ltd		Page 4
4, Ironstone Way Brixworth Northampton, NN3 9UD	25910 - Kestrel Way, Luton SW 1 in 1 Year FSR	
Date 13/12/2023 File Network 1.MDX	Designed by TL Checked by TL	
Innovyze	Network 2016.1	

Porous Car Park Manhole: S12, DS/PN: S3.001

Width (m) 4.8 Depression Storage (mm) 5
Length (m) 22.5 Evaporation (mm/day) 3
Slope (1:X) 60.0 Cap Volume Depth (m) 0.225

Tank or Pond Manhole: S13, DS/PN: S1.008

Invert Level (m) 121.300

Depth (m)	Area (m ²)	Depth (m)	Area (m ²)
0.000	65.0	1.200	65.0

Filter Drain Manhole: S16, DS/PN: S4.002

Infiltration Coefficient Base (m/hr) 0.00000 Pipe Diameter (m) 0.300
Infiltration Coefficient Side (m/hr) 0.00000 Pipe Depth above Invert (m) 0.000
Safety Factor 2.0 Number of Pipes 1
Porosity 0.30 Slope (1:X) 150.0
Invert Level (m) 123.340 Cap Volume Depth (m) 1.260
Trench Width (m) 0.6 Cap Infiltration Depth (m) 0.000
Trench Length (m) 18.0


Porous Car Park Manhole: S22, DS/PN: S5.000

Infiltration Coefficient Base (m/hr) 0.00000 Width (m) 4.8
Membrane Percolation (mm/hr) 1000 Length (m) 16.8
Max Percolation (l/s) 22.4 Slope (1:X) 60.0
Safety Factor 2.0 Depression Storage (mm) 5
Porosity 0.30 Evaporation (mm/day) 3
Invert Level (m) 122.595 Cap Volume Depth (m) 0.225

Tank or Pond Manhole: S23, DS/PN: S4.008

Invert Level (m) 121.265

Depth (m)	Area (m ²)	Depth (m)	Area (m ²)	Depth (m)	Area (m ²)
0.000	384.0	1.200	384.0	1.201	0.0

JPP Consulting Ltd		Page 5
4, Ironstone Way Brixworth Northampton, NN3 9UD	25910 - Kestrel Way, Luton SW 1 in 1 Year FSR	
Date 13/12/2023 File Network 1.MDX	Designed by TL Checked by TL	
Innovyze	Network 2016.1	

Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
Hot Start Level (mm) 0 Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 10
Number of Online Controls 1 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0


Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.408
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 20.000 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status OFF
DVD Status ON
Inertia Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
720, 960, 1440
Return Period(s) (years) 1
Climate Change (%) 0

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
S1.000	S1	15 Winter	1	+0%					123.731
S1.001	S2	15 Winter	1	+0%					123.615
S1.002	S3	15 Winter	1	+0%					123.355
S1.003	S4	15 Winter	1	+0%					123.119
S1.004	S5	15 Winter	1	+0%					122.785
S2.000	S6	15 Winter	1	+0%					122.961
S2.001	S7	15 Winter	1	+0%					122.477
S1.005	S8	15 Winter	1	+0%					122.281
S1.006	SHW1	15 Winter	1	+0%					122.095
S1.007	SHW2	15 Winter	1	+0%					121.894
S3.000	S11	15 Winter	1	+0%					123.049
S3.001	S12	15 Winter	1	+0%					122.542
S1.008	S13	30 Winter	1	+0%					121.499
S4.000	S14	15 Winter	1	+0%					123.745
S4.001	S15	15 Winter	1	+0%					123.495
S4.002	S16	15 Winter	1	+0%					123.458
S4.003	S17	15 Winter	1	+0%					123.366
S4.004	S18	15 Winter	1	+0%					123.329
S4.005	S19	15 Winter	1	+0%					123.175

JPP Consulting Ltd		Page 6
4, Ironstone Way Brixworth Northampton, NN3 9UD	25910 - Kestrel Way, Luton SW 1 in 1 Year FSR	
Date 13/12/2023 File Network 1.MDX	Designed by TL Checked by TL	
Innovyze	Network 2016.1	

Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Surcharged		Flooded		Pipe		Level Exceeded
		Depth (m)	Volume (m ³)	Flow / Cap.	Overflow (l/s)	Flow (l/s)	Status	
S1.000	S1	-0.119	0.000	0.44		16.9	OK	
S1.001	S2	-0.110	0.000	0.51		20.3	OK	
S1.002	S3	-0.180	0.000	0.33		27.8	OK	
S1.003	S4	-0.206	0.000	0.21		29.4	OK	
S1.004	S5	-0.215	0.000	0.18		32.7	OK	
S2.000	S6	-0.089	0.000	0.34		7.9	OK	
S2.001	S7	-0.073	0.000	0.51		7.9	OK	
S1.005	S8	-0.169	0.000	0.39		43.5	OK	
S1.006	SHW1	-0.155	0.000	0.47		43.8	OK	
S1.007	SHW2	-0.506	0.000	0.06		42.1	OK	
S3.000	S11	-0.101	0.000	0.23		8.1	OK	
S3.001	S12	-0.108	0.000	0.17		8.0	OK	
S1.008	S13	-0.401	0.000	0.11		30.8	OK	
S4.000	S14	-0.105	0.000	0.54		21.5	OK	
S4.001	S15	-0.165	0.000	0.41		21.7	OK	
S4.002	S16	-0.182	0.000	0.33		25.3	OK	
S4.003	S17	-0.154	0.000	0.47		25.3	OK	
S4.004	S18	-0.176	0.000	0.36		28.8	OK	
S4.005	S19	-0.170	0.000	0.39		28.6	OK	

JPP Consulting Ltd		Page 7
4, Ironstone Way Brixworth Northampton, NN3 9UD		25910 - Kestrel Way, Luton SW 1 in 1 Year FSR
Date 13/12/2023 File Network 1.MDX		Designed by TL Checked by TL
Innovyze		Network 2016.1



Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
S4.006	S20	15	Winter	1	+0%				123.062
S4.007	S21	15	Winter	1	+0%				122.724
S5.000	S22	15	Winter	1	+0%				121.955
S4.008	S23	360	Winter	1	+0%				121.464
S1.009	SFCC1	30	Winter	1	+0%	1/15 Summer			121.487

PN	US/MH Name	Surcharged Flooded			Pipe		Status	Level Exceeded
		Depth (m)	Volume (m³)	Flow / Cap. (l/s)	Flow (l/s)			
S4.006	S20	-0.198	0.000	0.25	35.1	OK		
S4.007	S21	-0.226	0.000	0.14	35.0	OK		
S5.000	S22	-0.095	0.000	0.29	6.0	OK		
S4.008	S23	-0.401	0.000	0.01	3.0	OK		
S1.009	SFCC1	0.087	0.000	0.24	3.5	SURCHARGED		