Please add Consultee comments to IDOX

Kind Regards

Oliver

Oliver Ashford BSc (Hons) MSc MRTPI Planning Officer

www.tendringdc.gov.uk

Tendring District Council, Town Hall, Station Road, Clacton on Sea, CO15 1SE

Tendring Map Access Portal (arcgis.com)

Click Here for Tendring DC Planning and Building Control Website and Contacts

From: Katie Wesley-Smith <

Sent: Friday, February 2, 2024 3:39 PM

To: Oliver Ashford <

Subject: 24/00136/FUL: Harewood Surgery, Harwich Road, Gt Oakley

Good Afternoon Oliver – with reference to the above application, please see below for comments from the EP Team:

<u>Contaminated Land:</u> Due to the sites proximity to a piece of registered, historical contaminated land, and the surrounding historical agricultural land, the EP Team are requesting that a Watching Brief be adhered to throughout the demolition and construction phases. We request that the LPA are contacted in the event of unexpected ground conditions being encountered during construction and that the below minimum precautions are undertaken until such time as the LPA responds to the notification. I would also advise that the developer is made aware that the responsibility for the safe development of the site lies with them.

Minimum requirements for dealing with unexpected ground conditions being encountered during construction.

- 1. All site works at the position of the suspected contamination will stop and the Local Planning Authority and Environmental Health Department will be notified as a matter of urgency.
- 2. A suitably trained geo-environmental engineer should assess the visual and olfactory observations of the ground and the extent of contamination and the Client and the Local Authority should be informed of the discovery.
- 3. The suspected contaminated material will be investigated and tested appropriately in accordance with assessed risks. The investigation works will be carried out in the presence of a suitably qualified geo-environmental engineer. The investigation works will involve the collection of solid samples for testing and, using visual and olfactory observations of the ground, delineate the area over which contaminated materials are present.
- 4. The unexpected contaminated material will either be left in situ or be stockpiled (except if suspected to be asbestos) whilst testing is carried out and suitable assessments completed to determine whether the material can be re-used on site or requires disposal as appropriate.

- 5. The testing suite will be determined by the independent geo-environmental specialist based on visual and olfactory observations.
- 6. Test results will be compared against current assessment criteria suitable for the future use of the area of the site affected.
- 7. Where the material is left in situ awaiting results, it will either be reburied or covered with plastic sheeting.
- 8. Where the potentially contaminated material is to be temporarily stockpiled, it will be placed either on a prepared surface of clay, or on 2000-gauge Visqueen sheeting (or other impermeable surface) and covered to prevent dust and odour emissions.
- 9. Any areas where unexpected visual or olfactory ground contamination is identified will be surveyed and testing results incorporated into a Verification Report.
- 10. A photographic record will be made of relevant observations.
- 11. The results of the investigation and testing of any suspect unexpected contamination will be used to determine the relevant actions. After consultation with the Local Authority, materials should either be: o re-used in areas where test results indicate that it meets compliance targets so it can be re-used without treatment; or o treatment of material on site to meet compliance targets so it can be re-used; or o removal from site to a suitably licensed landfill or permitted treatment facility.
- 12. A Verification Report will be produced for the work.

<u>Asbestos:</u> Adequate and suitable measures should be carried out for the minimisation of asbestos fibres during demolition, so as to prevent airborne fibres from affecting workers carrying out the work, and nearby properties. Only contractors licensed by the Health and Safety Executive should be employed. Any redundant materials removed from the site should be transported by a registered waste carrier and disposed of at an appropriate legal tipping site.

REASON: It is the responsibility of the developer to ensure the safe development of the site and to carry out any appropriate land contamination investigation and remediation works. The condition is to ensure the risks from land contamination to the future users of the land and neighbouring land are minimised, together with those to controlled waters, property and ecological systems, and to ensure that the development can be carried out safely without unacceptable risks to workers, neighbours and other offsite receptors

<u>Construction Activities</u>: In order to minimise potential nuisance caused by demolition/construction works, Environmental Protection recommend that the following below is conditioned;

No vehicle connected with the works to arrive on site before 07:30 or leave after 19:00 (except in the case of emergency). Working hours to be restricted between 08:00 and 18:00 Mondays to Saturdays (finishing at 13:00 on Saturdays) with no working of any kind permitted on Sundays or any Public/Bank Holiday whilst construction works and alterations are being carried out.

No materials produced as a result of the site development or clearance shall be burned on site.

No dust emissions should leave the boundary of the site

Adherence to the above condition will significantly reduce the likelihood of public complaint and potential enforcement action by Pollution and Environmental Control. The condition gives the best practice for Demolition and Construction sites. Failure to follow them may result in enforcement

action under nuisance legislation (Environmental Protection Act 1990), or the imposition of controls on working hours (Control of Pollution Act 1974).

REASON: to protect the amenity of nearby residential premises

Should you have any queries, do not hesitate to contact me.

Kind Regards

Katie

Katie W Smith BSc (Hons) MCIEH CEnvH Chartered Environmental Health Practitioner Environmental Protection Team Leader

Tel: Email: