



Notes:

- Existing woodland path
- Path finished with resin bound rubber and aggregate surface.
- Dark grey line either side of path indicate proposed handrails.
- Surfacing of porous concrete block paving
- Existing contours
- Trees with TPOs
- Group of trees with TPOs
- Tree canopy
- Root Protection Zone (RPZ)
- To be removed (This group of Sycamore are referred to as G21 in the Arboricultural Impact Assessment and grade as 'C')
- Mixed planting areas - see the mix planting palette
- Long season bulb planting
- Proposed trees

Soft Landscaping mixed planting palette

Shrubs; stated species and size

- 1nr. *Cornus sanguinea* : 40-60cm high; container 3L; branched; 4 breaks
- 2nr. *Corylus avellana* : 40-60cm high; bare-root 1+1; transplant - seed raised; branched; 2 breaks
- 9nr. *Ribes uva-crispa* : 30-40cm high; bare-root 1+0; seedling; branched; 2 breaks
- 5nr. *Ruscus aculeatus* : 30-40cm high; container 3L; several shoots; 3 breaks

Herbaceous; stated species and size

- 17nr. *Achillea ptarmica* : 50cc min. plug; established root 2-3 months minimum; September to April planting; British native-origin
- 17nr. *Angelica sylvestris* : container 1L; full pot; September to April planting; British native-origin
- 17nr. *Betonica officinalis* : 50cc min. plug; established root 2-3 months minimum; September to April planting; British native-origin
- 17nr. *Centaurea nigra* : container 1L; full pot; September to April planting; British native-origin
- 17nr. *Digitalis purpurea* : container 0.5L; full pot
- 17nr. *Dipsacus fullonum* : 50cc min. plug; established root 2-3 months minimum; September to April planting; British native-origin
- 17nr. *Galium album* : 50cc min. plug; established root 2-3 months minimum; September to April planting; British native-origin
- 17nr. *Geum rivale* : 50cc min. plug; established root 2-3 months minimum; September to April planting; British native-origin
- 17nr. *Primula vulgaris* : container 0.5L; full pot
- 17nr. *Silene dioica* : 50cc min. plug; established root 2-3 months minimum; September to April planting; British native-origin
- 17nr. *Silene flos-cuculi* : 50cc min. plug; established root 2-3 months minimum; September to April planting; British native-origin
- 17nr. *Stellaria holostea* : 50cc min. plug; established root 2-3 months minimum; September to April planting; British native-origin
- 17nr. *Viola odorata* : container 0.5L; full pot; September to April planting; British native-origin
- 17nr. *Viola riviniana* : container 0.5L; full pot; September to April planting; British native-origin

Ferns; stated species and size

- 17nr. *Dryopteris filix-mas* : container 3L; full pot
- 17nr. *Polypodium vulgare* : container 3L; full pot
- 17nr. *Polystichum setiferum* : container 3L; full pot

Trees; stated species and size

- 1nr. *Acer campestre* : 14-16cm girth; 400-450cm high; rootballed 3x; extra heavy standard; clear stem minimum 200cm; 5 breaks
- 2nr. *Prunus padus* : 16-18cm girth; 400-450cm high; container 45-85L; extra heavy standard; clear stem minimum 200cm

Long Season Bulb mix

Mix is made up of early-flowering yellow and orange Narcissus and white Narcissus. These two flowering periods are followed by a third, consisting of blue Camassias. After this Alliums extend the flowering period through to June.



Rev	Description	Date	Drawn	Checked
-----	-------------	------	-------	---------

Project: **Maghull HC Woodland**

Title: **Planting**

Date: 01/2024 NL

Scale: 1:200 @ A2 Drawn by:

Issue: Checked by:

Revision: A Dwg status:

Drawing No: **GGM 2608 23**

GROUNDWORK
 GREATER MANCHESTER
 Trafford Ecology Park
 Lake Road
 Trafford Park
 Manchester M17 1TU
 Tel: 0161 220 1000



19.2m

48

