



- NOTES
1. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY TEMPORARY WORKS AND SHORING TO ENSURE THE STABILITY OF ADJACENT STRUCTURES DURING THE COURSE OF THE WORKS.
 2. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY EARTHWORKS SUPPORT TO EXPOSED EXCAVATIONS.
 3. THE DESIGN, INSTALLATION AND MAINTENANCE OF TEMPORARY WORKS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, UNLESS DETAILED IN THE TENDER DRAWINGS.
 4. ALL CONCRETE TO BE GRADE C28/35, PLACED IN ACCORDANCE WITH THE SPECIFICATION AND BS EN 1992-1-1.
 5. COVER TO REINFORCEMENT:-
GROUND BEAMS - 50mm
GROUND SLAB - 25mm (TOP)
 6. MINIMUM LAPS TO REINFORCEMENT TO BE AS FOLLOWS:-
B10 - B25 40 DIA
MESH - 450mm
 7. ALL MASONRY TO BS EN 1996-1-1 AND BUILDING REGULATIONS PART A WITH A MAXIMUM UNIT WEIGHT OF 20kg.

B	ADJUSTED TO SUIT CLIENTS COMMENTS	TS	05.02.24
A	TEXT AND PRESENTATION ALTERED	TS	31.01.23
REV	DESCRIPTION	BY CHKD	DATE DATE

DESIGNERS CDM NOTES

ALL WORKS TO BE CARRIED OUT BY A COMPETENT CONTRACTOR, WORKING TO AN APPROVED SAFE SYSTEM OF WORK, INCLUDING A DETAILED RAMS DOCUMENT

RESIDUAL RISK REGISTER

IN ADDITION TO THE HAZARDS NORMALLY ASSOCIATED WITH THE TYPES OF WORK DETAILED ON THIS DRAWING, PLEASE NOTE THE FOLLOWING:

DESCRIPTION	IDENTIFIED RISK / HAZARD

davidsonwalsh
37 Prestbury Road | Cheltenham | Gloucestershire | GL52 2PT
+44 (0)1242 256495
www.davidsonwalsh.com

Client **UCAS**

Project **UCAS HQ
ROSEHILL
NEW BARN LANE
CHELTENHAM**

Drawing **REPLACEMENT BOUNDARY
WALL
SECTIONS & DETAILS**

APPROVAL			
Status	APPROVAL		
Scale	1:25 UNO	Leaf	A1
Drawn	J.T.	Date	19.01.23
Checked		Date	
Project No.	22146		
Drawing No.	01	Revision	B