

[Home](#)[About](#)[Sales](#)[Services](#)[Logistics](#)[Corporate](#)[Media](#)[Careers](#)[Contact](#)

Logistics - Vehicle Specifications

Walking Floor Trailers

Bulk Loose Material and Palletised Goods



Trailer Length	13.60m
Overall Width	2.55m
Overall Height	4.20 to 4.50m
Volume up to	110m ³
Additional Loading Clearance up to	3.00m
Safe Door Radius	1.35m
Min. Door Clearance (allowing safe door opening)	5.25m

Chipliner Trailers

Bulk Loose Material and Palletised Goods



Trailer Length	13.60m
Overall Width	2.55m
Overall Height	4.20 to 4.66m
Aperture Height (to pelmet)	2.69-2.990m
Volume up to	110m ³
Additional Loading Clearance up to	3.00m
Safe Door Radius	1.35m
Min. Door Clearance (allowing safe door opening)	5.25m

Urea-Based Resin Transport Trailer

For carrying Liquid Resin, used in board manufacture



Trailer Length	13.60m
Overall Width	2.55m
Overall Height	4.20m
Resin Tank Volume	18,000 litres

Tipper Units

Bulk Loose Material and Animal Feed transport



Trailer Length	11.50m
Overall Width	2.55m
Overall Height	3.80m
Fully Tipped Height	10.87m
Volume up to	57m ³
Safe Door Radius	1.90m & 1.10m
Min. Door Clearance (allowing safe door opening)	5.50m

Bulk Blower Unit

Bulk Loose Sawdust, Flake and Animal Feed transport



Trailer Length	11.00m
Overall Width	2.55m
Overall Height	3.93m
Safe Door Radius	1.90m & 1.10m
Min. Door Clearance (allowing safe door opening)	5.50m

Timber Crane Trailers

Roundwood Forestry and Milling Co-Product transport



Trailer Length	13.50m
Overall Width	2.55m
Overall Height	4.20-4.50m
Load Width	2.35m
Load Height	2.30-2.90m
Crane Max Radius	9.60m
Crane Max Loading at 9.60m	1100kg

Timber Crane and Drag Trailers

Roundwood Forestry and Milling Co-Product transport



Overall Length	18.00m
Overall Width	2.55m
Overall Height	4.20-4.50m
Prime Mover Load Length	6.90m
Trailer Load Length	6.20m
Load Width	2.35m
Load Height	2.30-2.90m
Crane Max Radius	7.90m
Crane Max Loading at 7.90m	1220kg

Eight Wheeled Unit

Bulk Loose Sawdust, Flake and Animal Feed transport



Overall Length	9.50m
Overall Width	2.55m
Overall Height	3.90m
Body Length	7.14m
Safe Door Radius	1.90m & 1.10m
Min. Door Clearance (allowing safe door opening)	5.50m

Small Trailer Combination

Bulk Baled and Palletised Sawdust and Flake transport



Overall Length	12.90m
Overall Width	2.55m
Overall Height	2.75m
Prime Mover Overall Length	7.00m
Prime Mover Body Length	5.00m
Trailer Length	4.85m

Mobile Chipper Unit

Cost effective on-site chipping of brash, arboricultural arisings and waste wood



Overall Length In Transit	7.62m
Overall Length In Use	10.97m
Maximum Width In Transit	2.55m
Maximum Width In Use	5.33m
Maximum Height In Transit	4.00m
Maximum Height In Use	7.00m
Maximum Crane Reach	7.62m
Chipper Power	400hp

A.W. Jenkinson Forest Products
Clifton Moor, Clifton, Penrith, Cumbria. CA10 2EY

T: 01931 712644

F: 01931 712641

info@awjenkinson.co.uk



© A.W. Jenkinson Forest Products 2021

[Remote Support](#)