



NOTES

1. All traffic signs shall comply with Chapter 6 of the Traffic Signs Manual.

2. The minimum lateral clearance between any area in which work is being carried out and the edge of the carriageway available to traffic shall be 0.2m for roads with a speed limit of 40 mph or less and 1.2m for motorways and roads with a speed limit of 50 mph or more.

3. Where necessary, signs to be positioned to suit existing works.

4. Coning shall be installed at 45° to the edge of carriageway, as generally indicated.

This Drawing is the property of Premier Traffic Management Ltd. It MUST NOT be copied in part or sent to a third party without written permission.

REV No	REV DETAILS	DATE	DRAWN BY:	CHECKED BY:	APPROVED BY:	DATE
			C PYE	TM		19 July 2023

Premier
TRAFFIC MANAGEMENT LTD

Unit 5 Eagle Industrial Estate,
Torre Road, Leeds, LS9 7QL.
Tel: 01302701013

CLIENT	PROJECT TITLE
	Rushford Phase 2

Key	Key
Works Area	Pedestrian crossing
Traffic Cones	
Quick Fit Sign	
Sign	
Traffic light head	
Pedestrian route	
Pedestrian barrier	

DESIGNER CHECK LIST	OVERHEAD STRUCTURES	RESTRICTION ON STOPPING WITHIN WORKS
Is an airlock system required? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	The overhead hazard may not be visible, particularly at night. Mark the extent of the hazard with blue cones and a white sleeve.	Signs to warn oncoming traffic; workers cannot see them and will be unaware of the works location.
Have we been informed of any overhead obstructions in GIS requirements? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Place green cones with white sleeves, one either side of the works access points, inside the works, not as part of the site boundary cone line.	The overhead hazard may not be visible, particularly at night. Mark the extent of the risk zone with blue cones with yellow sleeves carrying an electrical hazard symbol and message.
Have we been informed of any significant risk of people and plant interface? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Restriction on stopping within works	Vehicles stopping in any part of a deceleration zone just inside the works access or on a haul route increase the risk of work vehicle collisions. Place yellow cones with white sleeves inside the works throughout the no stopping zone as a reminder for drivers.

STATUS: FOR COMMENT FOR ISSUE CONSTRUCTED SCALE: N.T.S.

DRAWING No. PTM.CAD.1882.002

Address: Rushford Roundabout
Newton Aycliffe
DL5 6JA