

Verde Pine- Planting Schedule

Verde Pine - Refer to figure 300 Planting Plan

PLANTATIONS

1.5m centres =

No per m2 = 0.44

				PLOT NO:				Total
				1	2	5		
Mix 1: Woodland lodge mix	Common Name	Specification	Protection	% Mix	1234	1247	396	2877 Area (m ²)
Trees								
Abies koreana	Korean Fir	PG 10L	treeguard	10%	55	56	18	129
Acer campestre	Field Maple	BR 1+1 60-80	spiral	5%	28	28	9	65
Betula pendula	Siver Birch	BR 1+1 60-80	spiral	6%	33	34	11	78
Malus sylvestris	Crab Apple	BR 1+1 60-80	spiral	6%	33	34	11	78
Picea pungens	Blue Spruce	PG 15L	treeguard	10%	55	56	18	129
Pinus contorta	Lodgepole Pine	PG 5L	treeguard	10%	55	56	18	129
Pinus nigra subsp. Laricio	Corsican Pine	PG 15L	treeguard	10%	55	56	18	129
Prunus avium	Wild Cherry	BR 1+1 60-80	spiral	5%	28	28	9	65
Prunus domestica	Plum	BR 1+1 60-80	spiral	3%	17	17	6	40
Prunus pissardii	Cherry Plum	BR 1+1 60-80	spiral	3%	17	17	6	40
Sorbus aucuparia	Rowan	BR 1+1 60-80	spiral	6%	33	34	11	78
Shrubs								
Corylus avellana	Hazel	BR 1+1 60-80	spiral	6%	33	34	11	78
Crataegus monogyna	Hawthorn	BR 1+1 60-80	spiral	6%	33	34	11	78
Euonymus europaeus	Spindle Tree	BR 1+1 60-80	spiral	6%	33	34	11	78
Ilex aquifolium	Holly	PG 2L 40-60	treeguard	3%	17	17	6	40
Viburnum opulus	Guelder Rose	BR 1+1 60-80	spiral	5%	28	28	9	65
				100%	553	563	183	1299
				PLOT NO:				Total
				6				
Mix 2: North-east boundary	Common Name	Specification	Protection	% Mix	150			150 Area (m ²)
Acer campestre	Field Maple	BR 1+1 60-80	spiral	10%	7			7
Corylus avellana	Hazel	BR 1+1 60-80	spiral	7%	5			5
Crataegus monogyna	Hawthorn	BR 1+1 60-80	spiral	40%	27			27
Euonymus europaeus	Spindle Tree	BR 1+1 60-80	spiral	10%	7			7
Ilex aquifolium	Holly	PG 2L 40-60	treeguard	6%	4			4
Sorbus aucuparia	Rowan	BR 1+1 60-80	spiral	12%	8			8
Viburnum opulus	Guelder Rose	BR 1+1 60-80	spiral	15%	10			10
				100%	68			68

Verde Pine- Planting Schedule

MIXED NATIVE HEDGE

2 staggered rows at 300mm centres

		No per m = 7		PLOT NO:			3 4			
Hedgerow mix	Common Name	Specification	Protection	% Mix	128	14	142	Length (m)		
Acer campestre	Field Maple	BR 1+1 60-80	spiral	5%	3	1	4			
Betula pendula	Silver Birch	BR 1+1 60-80	spiral	10%	6	1	7			
Corylus avellana	Hazel	BR 1+1 60-80	spiral	5%	3	1	4			
Crataegus monogyna	Hawthorn	BR 1+1 60-80	spiral	30%	18	2	20			
Euonymus europaeus	Spindle Tree	BR 1+1 60-80	spiral	5%	3	1	4			
Ilex aquifolium	Holly	PG 2L 40-60	treeguard	5%	3	1	4			
Malus sylvestris	Crab Apple	BR 1+1 60-80	spiral	5%	3	1	4			
Prunus avium	Wild Cherry	BR 1+1 60-80	spiral	9%	6	1	7			
Prunus domestica	Plum	BR 1+1 60-80	spiral	3%	2	1	3			
Sorbus aucuparia	Rowan	BR 1+1 60-80	spiral	3%	2	1	3			
Viburnum opulus	Guelder Rose	BR 1+1 60-80	spiral	10%	6	1	7			
				90%	55	12	67			

SEED MIX

Sown as per manufacturer's instruction

Enhanced Grassland

Emorsgate EM2 Standard General Purpose Meadow Mixture

Open areas within the footpath network

		PLOT NO:				
		7	8	9		
100%		1288	75	2772	4135 Area (m ²)	

Marginal Mix

Emorsgate EP1 Pond Edge Mixture

Applied to pond and swale edges

		PLOT NO:			
		10	11		
100%		104	123	227 Area (m ²)	

Shady Mix

Emorsgate EW1 Woodland Mixture

Applied in the woodland planting areas to provide herb understorey.

		PLOT NO:				
		1	2	5		
100%		1234	1247	396	2877 Area (m ²)	