



# William Blyth

## HANDMADE ROOF TILES & POTTERY

William Blyth  
Est. 1840

### SANDED PLAIN TILE

Using traditional methods and our skilled craftsmen, William Blyth manufacture a range of handmade sanded nibbed plain tiles. Each tile is individually cut from a dowel of clay, hand sanded, shaped, trimmed and nail-holed. Once made each tile is placed onto a specially shaped drying rack, to help achieve a double camber.

Once dry our sanded plain tiles are then set amongst other tiles in the kilns where they are fired to 1010°C to ensure the best durability and longevity from our clay.

Combining the natural properties of alluvial clay and sand facing creates a tile full of character, each tile resembles the individual marks of the maker.

Our handmade sanded plain tiles also help to resemble the characteristic and aesthetics of reclaimed tiles, suitable for both restoration and new builds.

### Chestnut Brown

A genuine handmade tile with its dark tones of browns and variations in texture gives an instant aged look, perfect for new builds and restoration projects. This tile is well suited for matching in with existing buildings and surroundings.

### Technical Information

- Minimum Roof Pitch

---

35°

---

- Head lap minimum

---

65 mm

---

- Batten spacing

---

100 mm

---

- Size of tile

---

267 mm x 165 mm

---

- Cover capacity
-

60 per m<sup>2</sup>

- Profile Depth

16 mm

- Hanging length

247 mm

- Weight per tile

1.2 kg

- Weight as laid

72 kg per m<sup>2</sup>

- Quantity per pallet

1,000

- Weight per pallet

1.2 tonnes

- Batten size

Up to 450mm rafter  
centres: 38mm x 25mm  
Up to 600mm rafter  
centres: 38mm x 25mm

- Nail size / type

38 mm x 2.65 mm  
aluminium clout nails