

Tree Number	Tree Species	Height (m)	Calculated Stem Diameter (mm)	Number of Stems	Root Protection Area (Radius, m)	North (m)	South (m)	East (m)	West (m)	Crown Clearance (m)	Estimated No. of Yrs.	BS Category	Physiological/Structural Condition	Management/Remedial Recommendations
T1	Beech	18	920	1	11.04	8	9	8	10	2.5	20-40	B1/2	Mature. Showing good physiological form.	Carry out minor pruning work to SW side of canopy to facilitate development and arrest any potential nuisance. (Reduce lower branches by +/- 2.5m).
T2	Weeping willow	14	580	1	6.96	8	8	6	5	1.5	15-30	B1/2	Mature. Showing good physiological form. Characteristic aerial deadwood.	Remove aerial deadwood throughout canopy.
T3	Horse chestnut	13	520	1	6.24	6	7	5	6	1.5	15-30	B2	Mature. Showing good physiological form. Early cavity formation extending from base to approx. 1m. 1st branch is over-extended with signs of bark inclusion at union.	Reduce 1st branch by 20%.
T4	Cherry	9	370 & 410	2	6.63	5	5	6	7	1	20-40	B2	Semi-mature. Showing good physiological form. Small amount of characteristic aerial deadwood.	