



Tel, [REDACTED]
Mob, [REDACTED]
Email, [REDACTED]
Web, rs-electricalservices.co.uk
VAT No. 111104763
5 Eakring Rd, Bilsthorpe, Newark, Nott's, NG22 8PZ

ESTIMATE

Quote: 1784

Date: 15/08/2023

Customer Details

Farnsfield Parish Council
New Hill
Farnsfield
Newark
Nott's

Work Undertaken.

Electrical installation work for new aircon units.

Install new 8way, 3phase distribution board adjacent to incoming supply/meter etc.
(mains supply isolator to be organised to be installed by the council)

Install 3No. armoured cables connected to new DB and terminated to rotary isolator switches local to
3No. external aircon units.

Cables will be secured to the "beam" running at ceiling height in the hall way area.

Cables will be secured to the walls on the outside of the building.

Costs include cables terminated to rotary isolators with a 3m length of SY type cable left for
connection to main aircon unit.

Costs do not include any termination to aircon units. If this is required there will be an additional
charge of [REDACTED] to complete this plus any additional materials.

If I am selected to undertake the work a final estimate will be provided prior to work starting once all
the relevant information is provided. (aircon unit locations, exact cable runs and lengths etc)

Cost for completion of work. [REDACTED]

Cost for VAT. [REDACTED]

Total cost for completion of work. [REDACTED]

Thank You [REDACTED]