

## Additional Information.

### Main drain connection feasibility.

Main drain connection is not feasible as main sewer connection is situated, some 150 meters from site with an elevation to sewer of approximately 20 meters. See attached diagram. Main Sewer

### Non mains connection plan.

See file Block Plan

### Percolation Test results.

No percolation test has been undertaken. However the ensign10 tank is tested and approved to BSEN12566-3/A1:2009. Published test results of 11.5:19.2:8.4mg/ltr (BOD:suspended solids:ammonia).

The tank is designed for 10 people. The current application would bring the maximum usage to 6 people.