

Discharge of Condition 2 - Details of new materials and finishes

Element	Description	Image reference
Brickwork	Brick type: Michelmersh Hampshire Stock Plain Red and Dark Multi for headers. Coarse Textured Handmades. Size: 215 x 102.5 x 65 Brick bond: Flemish Joint profile: Flush Mortar colour: Cemex Braintree Light	
Roofing	Roofing type: Slate Size: 250 x 500mm Product: Cupa 12 Roof membranes: 1F Bitumous Felt See drawings 421360-04-81 and 04-82 for details of eaves and ridge.	
PV Slates and fixings	Product: GB Sol PV slates Fixing: stainless steel screws and hooks	
Rainwater goods	Material: galvanised steel Product: Alumasc Infinity Steel HRS50 Size: 125mm half round Outlets: 80mm Finish: galvanised Colour: Galvanised steel	
Oak horizontal boarding	Colour: European Oak Finish: sawn, uncoated, no treatment Size: 23 x 200mm Profile: Feather edge	