



Product Information

Ibstock Code:	A0257A
Type:	Wirecut Extruded
Facing Description:	Rusticated
Dry Brick Weight (kg):	2.2kg
Pack Quantity:	360
Packaging (standard):	Banded (Plastic)
Factory:	Aldridge

Technical Specification (to BS EN 771-1)

Brick Dimensions (L x W x H mm):	215x102x65
Size Tolerances Mean & Range:	T2 R1
Configuration:	Vertically Perforated
Voids (%):	23-28
Compressive Strength (N/mm ²):	25
Active Soluble Salts:	S2
Water Absorption (% weight):	13
Durability:	F1
Gross Dry Density (Sound Insulation) (Kg/m ³):	1380
Equivalent Thermal Conductivity "K" value 5% Exposed:	0.98
Initial Rate of Absorption (Suction Rate) (Kg/m ² /min):	0.9
EAN:	5036335028261