

COLOURED RENDERS

FASSACOUCHE



Semi-lightweight through-coloured render for protecting and decorating facades
Available in 25 colours (see colour chart)

Yield(*) approx. 13 kg/m² when applied to a thickness of 10 mm

Grading <1.6 mm

Water vapour diffusion resistance factor (EN 1015-19) μ ≤ 10 (measured value)

(*)Actual yield may vary depending on the type of finish required



Item code	Colour	Pack
1101E	BIANCHISSIMO	25 kg 48 packs/pallet
1102E	LUTECE	
1103E	IVOIRE	
1104E	MANHATTAN	
1105E	CHAMPAGNE	
1106E	PROVENCE	
1107E	NAPLES	
1108E	LUBERON	
1109E	TREVISE	
1110E	PECHE	
1111E *	ROSE DE SABLE	
1112E	CARAMEL	
1113E	ISTRIA	
1114E	TUSCANIA	
1115E *	PERGAMON	
1117E	BOGNEC	
1120E *	AUVERGNE	
1121E	SIENNE	
1122E *	BRIQUE	
1124E *	OPAL	
1126E *	GRES	
1127E *	TRAVERTIN	
1129E	GRIS PERLE	
1130E	GRIS CENDRE	
1133E	CRÈME	

***COLOURS PRODUCED ON DEMAND WITH A MINIMUM ORDER OF 4 PALLETS AND A 5 WORKING DAYS' NOTICE TIME FOR PRODUCTION.**

The colours shown here are purely illustrative and can vary even significantly depending on site applications conditions. We recommend that you consult our samples. Due to the nature of the raw materials used (natural sands), uniformity of colour cannot be guaranteed between different supply lots. As a result, it is recommended that all the material required to finish the job should be acquired from the same batch.

Application of the product must be carried out strictly in accordance with BBA certificate 18/5486, the Certificate holder's instructions and the relevant recommendations of BS EN 13914-1: 2016.