



**ALEXANDRA ROAD**

**DRIVE**

**NORTH**

ex BT pole repositioned  
street lamp repositioned

hatching denotes footpath widening

ex BT pole relocated

ex BT pole removed

ex BT pole removed

**Foul Drainage**

Ref	Cover Level	Invert Level	Depth	Size	Material	Cover/frame size/ Grade	Remarks
FC1	19.55	19.20	0.35m	475mm dia	plastic	475mm dia class b metal	in patio
FC2	19.55	19.15	0.40m	475mm dia	plastic	475mm dia class b metal	in patio
FC3	19.55	19.00	0.55m	475mm dia	plastic	475mm dia class b metal	in patio
FC4	19.55	18.98	0.57m	475mm dia	plastic	475mm dia class b metal	in patio
FC5	19.55	18.86	0.69m	475mm dia	plastic	475mm dia class b metal	in patio
FC6	19.55	18.84	0.71m	475mm dia	plastic	475mm dia class b plastic	in patio
FC7	19.25	18.69	0.56m	475mm dia	plastic	475mm dia class c plastic	in paving drive
FC8	19.65	19.17	0.47m	225mm dia	plastic	225mm dia class b metal	in patio
FC9	19.65	19.25	0.40m	225mm dia	plastic	225mm dia class c plastic	in patio
FC10	19.65	19.27	0.38m	475mm dia	plastic	475mm dia class c plastic	in patio
FC11	19.65	19.30	0.35m	475mm dia	plastic	475mm dia class b metal	in patio

- Denotes crated soakaway
- Denotes Foul Sewer Diversion
- Denotes storm drains
- Denotes foul drains
- Denotes insitu concrete capping to drains under drives
- Denotes permeable pavior finish

X Denotes 7.0kw car charging point