


PROPOSED GROUND FLOOR



GENERAL

Allow for all site dimension checking before and during construction work.
 Construction to comply with all provisions of the current Building Regulations.
 Formation levels: final formation levels to be determined on site and agreed with CA and Building Inspector.
 Structural timber: strength class C16 as defined in BS. 5268 Part 2 : 2002
 Preservative treatment to structural and non structural timber: British Wood Preserving and Damp Proofing Commodity Specification C8, service life 40 years.

PARTY WALL

The owner, should they need to do so under the requirement of the Party Wall Act 1996, has a duty to serve a Party Structure Notice on any adjoining owner if building work on, to or near an existing Party Wall, Structure.
 A Party Wall Agreement is to be in place before any construction/ demolition to be carried out

SUBSTRUCTURE


Remove all trees, undergrowth and re-grade to required levels, remove all topsoil, vegetable matter and deleterious material, excavate for foundations to suit site conditions, to approval.
 Concrete strip foundation, mix C20P to project 150 mm from wall face, minimum 250 mm thick and 1000mm below finished ground level, all to suit site conditions, to approval
 Foundation profiles are to be altered as necessary to allow passage of services and drainage without risk of differential settlement.
 Class B semi-engineering brickwork to BS: 3921 laid in mortar mix 1:4, cement:sand; below Hyload or similar damp-proof course minimum 150 mm above finished ground level, lean mix cavity fill to 225mm below damp-proof course, weep holes @ 900 mm centres. For thickness of walls, refer to drawings.
 Marley "Dampseal" vertical damp-proof membrane/tanking to manu. details to seal and waterproof all changes in level, thoroughly sealed to damp-proof courses.
 Cavity Wall to Boundaries to have 1000 x 1000mm excentric foundation at a formation level to be agreed on site with building inspector

DRAINAGE

Allow for checking all existing drainage runs to confirm proposed drainage layout assumed is correct, if not contact supervisor/ site manager asap to have drawings revised.
 Hepworth pvc pipes with flexible joints, size DN100 and DN150. and fittings with pressure tight flexible joints, lintols over pipes passing through walls, fibreglass sleeved and surrounded with 150 mm pea gravel or concrete where less than 150 mm below floor slab. Soil and vent pipe connections direct to inspection chambers, gully branches to suit site conditions, all to manu. details and Local Authority approval.
 Drain gradients: DN100 1:40, DN150 1:60 unless otherwise noted
 Drain levels: contractor to check all levels given prior to commencing the works. Where new sewer connection is required check invert level of connection prior to installing new drainage on site.
 Drain bedding generally: Class F granular bed. Drainbedding of shallow drains within 300 mm of underside of slab: Class Y encased in 150 mm integral with slab, concrete mix as slab. Drain bedding under buildings: Class W 100 mm granular surround.
 Drainage trenches liable to surcharge from adjoining foundations are to be backfilled to above the level of surcharge with class Z 150mm mix GEN 3 to BS5328 and with build in 18 mm Flexell sleeves through pipe joints at maximum 9 metre centres.
 Access to all parts of the drainage system is to be provided by inspection chambers and rodding eyes as shown on drawings, to approval.
 Small inspection chambers are to be plastic used within the depth and number of connection limitations as prescribed by the manufacturer. to BS7518

EXTERNAL WALL

Cavity fill: Render on 100 mm blockwork to approved sample in 1:1:6; cement: lime: sand mortar, 150 mm cavity with triangular stainless steel cavity ties @ 750 mm centres horizontally and 450 mm centres vertically (225 mm centres vertically to unbonded jambs), 150mm "Dritherm 32" cavity insulation board, 100 mm Marley "Aguaguard" or similar flexible vertical damp-proof courses, 100 mm Thermalite Turbo blockwork inner leaf 2.9 N to BS 6073 Part 1 throughout, finished with minimum 12.5mm plasterboard on dabs and skimmed, 'U' value 0.18 W/sq.m deg C, including Thermabate closers to reveals and to eaves and verges, galv. expanded metal reinforcement over soldier courses. Cavity walls To boundary not to be replaced with blockwork.
 Cavity walls with steel beams bearing to have 7N blockwork with 25mm Kingspan insulation dry lining.
 Install minimum two course high proprietary cavity tray stepped to suit raking abutments where roofs abut external walls as manu. by Glidevale or Cavity Trays Ltd. Trays to terminate by dressing down onto Code 4 lead flashings.

		202 Spies Lane, Halesowen, West Midlands, B62 9SW	
		11 ST MARYS ROAD WEDNESBURY WEST MIDLANDS WS10 9DL	
Project	PROPOSED GROUND SINGLE STOREY REAR EXTENSION		
Drawing No	2303.03	A3	Date JAN 2024
Scale	1:50, 1:55	Drawn	MF
<small>This document and its design content is copyright © of TDF Design Limited and should not be reproduced in part or whole without permission. It shall be read in conjunction with all other associated project information including models, specifications, schedules and related consultants documents. All dimensions to be checked on site, immediately report any discrepancies, errors or omissions on this document to the Originator. If in doubt ASK.</small>			
Rev	Comment	Date	