

FZ Wall Mounted Indoor Unit - Split - R32

Product Code: CS-FZ50WKE

Wall Mounted - Single Phase- R32

Notes

- » Compact and elegant design with only 779mm wide
- » Cleaner air with PM2,5 Filter
- » Super Quiet! Only 20dB(A)
- » More comfort with Aerowings
- » High energy savings: A++
- » Optional internet and voice control
- » Long piping length
- » These units can be installed on R410A and R22 pipings



MODEL NUMBER		CS-FZ50WKE
GRILLE		NA
Nominal cooling (min-max)	kW	5.00 (0.98 - 5.40)
Nominal heating (min-max)	kW	5.40 (0.98 - 7.50)
Height	mm	290 x 779 x 209
Width	mm	290 x 779 x 209
Depth	mm	290 x 779 x 209
Weight	kg	8
Knock out for fresh air intake		N/A
Knock out for branch duct		N/A
Indoor unit airflow rate (cool - heat)	m ³ /min	12.5/13.2
Moisture Removal Volume	l/h	2.8
Static pressure	pa	NA
Spigot Kit		N/A
Discharge spigot		NA
Sound pressure level heat (h-m-l)	dB(A)	44 / 37 / 34
Sound pressure level cool (h-m-l)	dB(A)	44 / 37 / 34
Pipe connection size - gas	in	1/2 (12.70)
Pipe connection size - liquid	in	1/4 (6.35)
Refrigerant		R32
Drain connection	mm	VP13 (18mm OD)
Lift pump?		No
Power supply	V-Ph-Hz	From Indoor or Outdoor
Interconnecting cables		3 Core & E
Suggested fuse size		13
Controller included?		Yes - Infrared

* exact cooling and heating capacities will depending on connected outdoor unit and system configuration