

Multi Split System - Free Multi Z

Product Code: CU-4Z80TBE



MODEL NUMBER		CU-4Z80TBE
System Capacity (Min - Max)		4.5 to 14.7 kW
Nominal Cooling (Range)	kW	8.00 (3.00 - 9.20)
Nominal Heating (Range)	KW	9.40 (4.20 - 10.60)
Number Of Indoor Units		2 - 4
EER - COP (Cool - Heat)		4.04 - 4.52
SEER - SCOP (Cool - Heat)		7.00 - 4.00
Energy Efficiency Class (Cool / Heat)		A++ / A+
Annual Electricity Consumption Cool - Heat		— — —
Pdesign (cooling)	kW	8
Heating capacity at -7°C	kW	—
Pdesign at -10°C	kW	8
Operating Range -Cooling	°C	-10°C to 46°C
Operating Range - Heating	°C	-15°C to 24°C
Height	mm	999
Width	mm	940
Depth	mm	340
Weight	kg	80
Sound Pressure Level (Cool-Heat)	dB(A)	—
Gas Pipe Size*	in	3/8"
Liquid Pipe Size*	in	1/4"
Min - Max Pipe Run (Per Unit)	m	3 - 25
Min - Max Pipe Run (Total)	m	—
Maximum Height Difference	m	15
Pre-charged for	m	-
Charge R32 - Factory	Kg	TBC
Charge R32 - Additional	g/m	-
Power Supply (Outdoor)	V-Ph-Hz	230 - 1 - 50
Suggested Fuse Size	A	20
Power Input (Cool - Heat)	kW	0.80 - 0.95
Running Current (Cool - Heat)	A	—
* exact cooling and heating capacities will depending on connected indoor unit and system configuration		